



**Universiteit
Leiden**

The Netherlands

Analecta Praehistorica Leidensia 33/34 / Sacrificial Landscapes : cultural biographies of persons, objects and 'natural' places in the Bronze Age of the Southern Netherlands, c. 2300-600 BC

Fontijn, David R.; Fokkens, Harry; Bakels, Corrie

Citation

Fontijn, D. R. (2002). Analecta Praehistorica Leidensia 33/34 / Sacrificial Landscapes : cultural biographies of persons, objects and 'natural' places in the Bronze Age of the Southern Netherlands, c. 2300-600 BC, 392. Retrieved from <https://hdl.handle.net/1887/33737>

Version: Not Applicable (or Unknown)
License: [Leiden University Non-exclusive license](#)
Downloaded from: <https://hdl.handle.net/1887/33737>

Note: To cite this publication please use the final published version (if applicable).

ANALECTA PRAEHISTORICA LEIDENSIA

33/34

PUBLICATION OF THE FACULTY OF ARCHAEOLOGY
UNIVERSITY OF LEIDEN

DAVID R. FONTIJN

SACRIFICIAL LANDSCAPES

CULTURAL BIOGRAPHIES OF PERSONS, OBJECTS AND 'NATURAL' PLACES
IN THE BRONZE AGE OF THE SOUTHERN NETHERLANDS, C. 2300-600 BC



UNIVERSITY OF LEIDEN 2002

Editors: Harry Fokkens / Corrie Bakels

Copy editors of this volume: David Fontijn / Harry Fokkens

Copyright 2002 by the Faculty of Archaeology, Leiden

ISSN 0169-7447

ISBN 90-73368-19-7

Also appeared as doctorate thesis, Leiden, March 27, 2003.

Subscriptions to the series *Analecta Praehistorica Leidensia*
and single volumes can be ordered exclusively at:

Faculty of Archaeology
P.O. Box 9515
NL-2300 RA Leiden
the Netherlands

*Non multo post in Cantabriae lacum fulmen decidit repertaeque sunt duodecim
securae, haud ambiguum summae imperii signum.*

(Suetonius, book VII: Galba, Otho, Vitellius)

*Und dast Sterben, dieses Nichtmehrfassen
Jenes Grunds, auf dem wir täglich stehn,
Seinem ängstlichen Sich-Niederlassen -:*

*In die Wasser, die ihn sanft empfangen
Und die sich, wie glücklich und vergangen,
Unter ihm zurückziehn, Flut um Flut*

(R.M. Rilke 'der Schwan')

contents

Preface xvii

PART I PROBLEM, APPROACH, SOURCE CRITISM 1

1 Introduction: the problem of bronze deposition and the aim of this study 3

1.1 Introduction 3

1.2 The social significance of metalwork among European Bronze Age societies 3

1.3 The phenomenon of bronze deposits and its interpretation as ‘ritual consumption’ 5

1.4 Problems in the current interpretation of bronze deposits: ‘selective deposition’ 5

1.5 The southern Netherlands as a promising region for studying ‘selective deposition’ 6

1.6 Research questions and spatial and chronological framework 6

1.7 How the problem will be approached 9

2 How archaeology has made sense of object depositions: the distinction between ‘ritual’ and ‘profane’ deposits 13

2.1 Introduction 13

2.2 Seeing bronze deposits primarily in profane terms: *Verwahrkunde* and *Versteckfunde* 13

2.3 Accepting bronze finds as permanent deposits and interpreting them as ‘ritual’ 15

2.3.1 The distinction between ‘ritual’ and ‘profane’ depositions 15

2.3.2 Levy’s theory: is the Bronze Age ritual-profane distinction supported by ethnographic parallels? 17

2.4 *Explaining* ritual deposition: economic and competitive consumption 18

2.5 How ‘ritual’ is reconciled to assumptions on the universality of rationality 19

2.6 Problems we face when using the ‘ritual/ profane’ distinction for the interpretation of deposits 20

2.6.1 Problems raised by the empirical evidence 20

2.6.2 Epistemological problems 20

2.7 How can we get round the problems of the ‘ritual/profane’ distinction? 21

2.8 Final remarks 21

3 Theoretical framework for the study of selective deposition 23

3.1 Introduction 23

3.2 The concept of ‘meaning’ 23

3.3 Objects as ‘things’ and objects that are ‘like persons’ 25

3.4 How meaning comes about: the cultural biography of things 26

3.5 Kinds of biographies: valuables associated with communal versus personal identities 26

3.6 The start of a biography: production 27

3.6.1 The crucial position of the smith as a creator of potential valuables 27

3.6.2 Material and techniques 28

3.6.3 Concept of form and style 28

3.6.4 Functional possibilities 30

3.7 The life of an object 30

3.7.1 Metalwork circulation as an exchange of gifts *and* commodities; long-term and short-term exchange 31

3.7.2 Transformation of commodities into gifts or valuables and the archaeological indications that they took place 31

3.7.3 The archaeological correlates for circulation 32

3.7.4 The archaeological correlates for ‘use’ 32

3.7.5 The deposited objects as a skewed representation of the objects in circulation 33

3.8 Deposition 33

3.8.1 The practice of deposition as constituted by relations between object, people and location 33

3.8.2 Deposition as performance 35

3.8.3 What deposition brings about 35

3.9 Concluding remarks 35

4 Source criticism: limitations and possibilities of the available evidence 37

4.1 Introduction 37

4.2 How to recognize permanent depositions 37

4.3 How the data were collected and evaluated 38

4.3.1 Assessing the reliability of data 39

4.3.2 Retrieving information on find context 41

- 4.4 Explaining presence and absence of finds: post-depositional processes 42
- 4.4.1 Natural processes 43
- 4.4.2 Anthropogenetic processes 43

4.5 Explaining presence and absence of finds: research factors 45

4.6 Conclusion: which set of data is informative on selective deposition? 45

PART II SELECTIVE DEPOSITION THROUGHOUT THE BRONZE AGE 53

5 Late Neolithic B and Early Bronze Age 55

5.1 Introduction 56

5.2 Late Neolithic and Early Bronze Age societies in the southern Netherlands 57

5.3 Discussion of the available evidence 60

5.4 Late Neolithic metalwork 60

5.4.1 Local production and the 'Dutch Bell Beaker metal' 61

5.4.2 Flat axes 63

5.4.3 The double axe from Escharen 65

5.4.4 Gold ornaments 66

5.4.5 Daggers 67

5.4.6 Conclusion: selective deposition in the Late Neolithic B? 68

5.5 Early Bronze Age metalwork 68

5.5.1 Low-flanged axes 68

5.5.2 Halberds 71

5.5.3 The Wageningen hoard 72

5.5.4 Metalwork from burials and settlements 73

5.5.5 Conclusion: selective deposition in the Early Bronze Age? 74

5.6 From stone to bronze 75

5.6.1 How metal replaced stone in daily life 75

5.6.2 The cultural attitude towards metals and stones 75

5.6.3 The life of metals and new elements in the cultural biography of things 76

5.7 Patterns in the biographies of metalwork: production and circulation 77

5.7.1 Circulation: the importance of being imported 77

5.7.2 Open systems: the interplay between imported objects and local products 78

5.8 Deposition: the incorporation of metalwork in Neolithic offering traditions and their subsequent transformation 78

5.8.1 Continuity and change 78

5.8.2 Fluctuations in the rate of deposition 79

5.8.3 Conclusion 79

5.9 Deposition: graves and wet places as contrasting depositional contexts 79

5.9.1 The Beaker burial ritual and the significance of objects as valuables of personhood 80

5.9.2 The deposition of axes in wet places 82

5.10 Conclusions 83

6 Middle Bronze Age A 85

6.1 Introduction 86

6.2 The transition from Early to Middle Bronze Age: developments in society and landscape 86

6.3 Discussion of the available evidence 87

6.4 High-flanged and stopridge axes 88

6.4.1 Oldendorf axes 88

6.4.2 Nick-flanged or *geknickte* axes 91

6.4.3 Atlantic imports? Arretton axes and axes with high-placed short-flanges 93

6.4.4 Two ‘unique’ axes 93

6.4.5 Stopridge axes 96

6.4.6 Conclusion 97

6.5 Spears 97

6.6 ‘Swords’ and daggers 100

6.6.1 Dirks, rapiers and daggers of the Sögel, Wohlde, Weizen and Gamprin types 100

6.6.2 The Overloon weapon hoard: the deposition of personal warrior sets 103

6.6.3 Tréboul-St. Brandan swords 103

6.6.4 The ceremonial dirk from Jutphaas 104

6.6.5 Other finds: two daggers of British type 105

6.6.6 Sword biographies 105

6.7 Developments in the structure of the metalwork repertoire 106

6.7.1 The category of specialized weapons and what it implies: the significance of martiality 106

6.7.2 Transformations in existing material culture categories 107

6.8 Metalwork circulation 107

6.8.1 The restructuring of spheres of exchange? 107

6.8.2 The southern Netherlands in the north-west European world 109

6.8.3 Bronze circulation and the problem of the ‘Hilversum culture’ 109

6.9 Patterns in metalwork deposition 110

6.9.1 Fluctuations in the rate of deposition 110

6.9.2 Axe deposition 110

6.9.3 Weapon deposition as the surrender of the paraphernalia of personhood 111

6.9.4 Conclusion 112

6.10 Conclusions 112

7 Middle Bronze Age B 115

7.1 Introduction 116

7.2 Landscape and society during the Middle Bronze Age B 116

7.3 Discussion of the available evidence 116

7.4	Palstaves and mid-winged axes	119
7.4.1	Imported palstaves	119
7.4.2	Regional palstaves	121
7.4.3	Mid-winged axes	125
7.4.4	The Goirle axe: the remarkable life-path of an old, much-travelled axe	127
7.4.5	Conclusion: axe biographies	129
7.5	Spearheads	129
7.6	Swords and daggers	131
7.6.1	Rosnoën swords	132
7.6.2	Other <i>Griffplatten</i> - and <i>Griffangelschwerter</i>	133
7.6.3	Reworked sword blades	133
7.6.4	Conclusions: life-cycles of swords	133
7.7	Ornaments	134
7.8	Sickles and other tools	137
7.9	Moulds	137
7.9.1	The bronze mould from Buggenum	138
7.9.2	The clay mould from Cuijk	138
7.9.3	The clay mould from Oss-Horzak	138
7.9.4	Conclusions	141
7.10	Metalwork and contemporary material culture	141
7.11	Regional bronze production	142
7.12	Metalwork circulation	143
7.12.1	General developments: reorientation of exchange networks	143
7.12.2	Patterns of procurement	143
7.13	Deposition	144
7.13.1	Deposition in and around houses	144
7.13.2	Axe and weapon deposits: depositional zones as places of historical significance	147
7.13.3	Deposition of objects in burials	147
7.13.4	Deposition of objects in burial monuments	148
7.14	Conclusions	148
8	Late Bronze Age	151
8.1	Introduction	152
8.2	Society and landscape during the Late Bronze Age	152
8.2.1	North-western Europe	152
8.2.2	Southern Netherlands	154
8.3	Discussion of the available evidence	154

8.4	Socketed and end-winged axes	157
8.4.1	Regional socketed axes	157
8.4.2	Imported socketed axes	161
8.4.3	End-winged axes	164
8.4.4	Iron axes	164
8.4.5	Conclusions	165
8.5	Weapons: spears, swords, chapes and daggers	166
8.5.1	Early <i>Griffzungenschwerter</i>	166
8.5.2	The <i>Vielwulstschwert</i> from Buggenum	166
8.5.3	The weapon hoard from Pulle	169
8.5.4	<i>Griffzungen</i> - and <i>Vollgriffschwerter</i> from the Ha B2/3 phase	170
8.5.5	Gündlingen swords	171
8.5.6	Mindelheim swords	172
8.5.7	Conclusion: sword biographies	172
8.6	Ornaments and dress fittings	172
8.6.1	Deposition in major rivers	175
8.6.2	Deposition of ceremonial ornaments: the giant <i>Bombenkopfnadel</i> of type Ockstadt	175
8.6.3	Ornaments in multiple-object hoards	178
8.6.4	Conclusion: selective deposition of ornaments	182
8.7	Other tools	182
8.8	The place of metalwork among contemporary material culture	184
8.9	Regional bronze production	186
8.10	Metalwork circulation	186
8.11	Deposition	187
8.11.1	Axe and tool deposition	187
8.11.2	Weapon and ornament deposition: evidence for a structured sacrificial landscape?	188
8.11.3	New places for deposition?	191
8.11.4	Change and tradition in the practice of deposition	192
8.12	Conclusions	193
9	Late Bronze Age and Early Iron Age: metalwork from burials	197
9.1	Introduction	197
9.2	Discussion of the available evidence	197
9.3	The urnfield burial ritual and the provision of artefacts	197
9.4	Ornaments and toilet articles in urnfield graves	198
9.5	Deposition of weaponry	201
9.6	Stages in the burial ritual and the inclusion of artefacts	203

9.7	The decorated dead	204
9.8	Local and supra-local personal identities	206
9.9	Conclusions	207
PART III UNDERSTANDING SELECTIVE DEPOSITION		209
10	Selective deposition: its characteristics, development and structure	211
10.1	Introduction	211
10.2	Some general characteristics of metalwork deposition	211
10.3	The long-term patterns of selective deposition	215
10.4	Selective deposition as an indication that different objects had different meanings	215
10.5	How objects became meaningful: the significance of their cultural biography	217
10.6	Depositions in burials versus depositions in natural places	217
10.7	Long-term history of selective deposition	218
10.8	Development of the argument in the next chapters	219
11	Weapons, the armed body and martial identities	221
11.1	Introduction	221
11.2	The distinction between multifunctional tools and weapons before the Middle Bronze Age	221
11.3	Weapons of the Middle and Late Bronze Age	221
11.4	The nature of Bronze Age conflicts and warfare	224
11.5	Warfare as ideology	226
11.6	Warrior identities	226
11.6.1	Sword fighting and becoming a person	227
11.6.2	The evidence of warriors' graves	227
11.6.3	Warrior identities and 'imagined communities'	229
11.7	Weapon deposits as graveless grave goods?	229
11.8	Warriorhood as an ambiguous, temporary identity	231
11.9	The shift from rivers to graves	232
11.9.1	Ha C chieftains' graves as reflecting a different kind of elite?	232
11.9.2	How did a shift to burial deposition become socially acceptable?	233
11.9.3	Conclusion: the continuing ambiguity of warrior statuses	236
11.10	Conclusions	236

12 Ornament deposition: the construction and deconstruction of personhood 239

12.1 Introduction 239

12.2 Ornament deposition in natural places versus deposition in burials 239

12.3 Selective deposition of ornaments and dress fittings during the Middle Bronze Age 239

12.4 The significance of supra-regional ornament styles: the implications of the Oss mould 240

12.5 Selective deposition of ornaments and dress fittings during the Late Bronze Age 241

12.5.1 Ornaments and the construction of local identities in urnfield graves 241

12.5.2 Placing ornaments and pins in rivers and sources 241

12.5.3 Deposition of special ornament types in hoards: the Lutlommel hoard 242

12.6 Conclusion: the contrast between local and non-local identities 244

13 The cultural biographies of axes 247

13.1 Introduction 247

13.2 The significance of imported adzes and axes for non- or semi-agrarian communities 247

13.3 The deposition of single, used bronze axes: the generalized biography of an axe 248

13.4 There is more to axes than just the tool 250

13.5 Late Bronze Age axe hoards 252

13.6 Axe hoards as representing deliberate permanent deposits 252

13.7 Linking 'ritual' deposition to the flow of metal 253

13.7.1 How gift and commodity exchange are linked 254

13.7.2 Object deposition as a way to transform items from commodities into gifts 255

13.8 What happened at the transition from the Late Bronze Age to Iron Age? 255

13.8.1 Understanding lavish hoards in relation to a collapsing bronze circulation 256

13.8.2 Changes within the depositional practices themselves 256

13.9 Conclusions 257

14 The landscape of deposition 259

14.1 Introduction 259

14.2 Deposition in a historical landscape 259

14.2.1 The system of selective deposition as reflecting structured perceptions of the land 259

14.2.2 Multiple-deposition zones and the landscape of memory 260

14.2.3 What does the difference between adjacent multiple deposition zones imply? 263

14.3	Deposition and the landscape of daily life	264
14.3.1	Depositional zones as remote and peripheral areas	264
14.3.2	Depositional zones as natural, unaltered places	264
14.4	Depositional zones in a social landscape	265
14.5	Depositional zones in a cosmological landscape	266
14.5.1	Wet zones as cosmological boundaries	266
14.5.2	Deposition in watery places: gifts to gods?	267
14.6	Deposition and cultural attitudes towards the land	268
14.6.1	Exploitative and communalist attitudes	268
14.6.2	Depositions and notions on reciprocal relations with the land	269
14.6.3	Depositions and the logic of taking and giving	269
14.7	Depositional practices and the construction of communities	270
14.8	Conclusions	271

15 Final reflections: what is selective deposition and what does it bring about? 273

15.1	Introduction	273
15.2	Circulation of foreign materials and social realities	273
15.3	Bronzes and the significance of non-local identities	274
15.4	Accepting <i>their</i> logic: a sacrificial economy	274
15.5	Deposition as a practice	275
15.6	Deposition as ritual	276
15.7	What does selective deposition bring about?	277

epilogue 281

references 285

appendices 305

1	List of all hoards from the study region	305
2.1	Flat axes	310
2.2	Low-flanged axes	311
2.3	Oldendorf axes	312
2.4	Other MBA A axes	314
2.5	Imported palstaves and other axes	315
2.6	Regional palstaves, midribbed	317
2.7	Regional palstaves, plain sinuous-shaped and those with trapeze outline	318
2.8	Unclassified palstaves	320

2.9	Mid-winged axes	321
2.10	Socketed axes of the Niedermaas type	322
2.11	Socketed axes of the Helmeroth type	324
2.12	Socketed axes of the Geistingen type	325
2.13	Socketed axes of the Plainseau type	326
2.14	Socketed axes of type Wesseling	328
2.15	Other socketed axes, Early Iron Age axes, iron axes	329
2.16	End-winged axes	332
3	Sickles, knives, chisels, gouges from the Middle and Late Bronze Age	333
4.1	Ornaments mainly from the MBA B	335
4.2	Ornaments from the LBA/EIA from other contexts than graves	336
5.1	Swords and daggers from the MBA A	338
5.2	Swords and daggers from the MBA B	339
5.3	Swords from the Ha A2 (A1) until Ha B1 phases	341
5.4	Swords from the Ha B2/3 phase	342
5.5	Swords from the Early Iron Age (made of bronze and iron)	343
5.6	MBA swords from the Netherlands and Belgium: deposition in graves versus deposition in watery places	345
6.1	Spearheads from the MBA A	348
6.2	Spearheads from the MBA B	349
6.3	Spearheads without precise dating (plain pegged spearheads) and arrowheads	350
7.1	Daggers, knives, halberds and ornaments from the LN B/EBA, mainly from burials	356
7.2	Burial gifts from the MBA and deposits in barrows (metalwork and other materials)	358
7.3	Metalwork from urnfield graves in the Dutch part of the research region	361
7.4	Metalwork from urnfield graves in the Belgian part of the research region	370
8	Indications for metalworking (Middle and Late Bronze Age)	373
9	Metalwork finds from settlements	374
10.1	Metal types distinguished by Butler and Van der Waals	376
10.2	Metal analyses of flat and low-flanged axes	376
10.3	Metal analyses of tanged daggers and awls from burials	377
10.4	Metal analyses of halberds, riveted knives and an awl	377
10.5	Metal analyses of objects from the Wageningen hoard	378

samenvatting (Dutch summary) 379

acknowledgements for the figures 389

acknowledgements 391

9.1 INTRODUCTION

The last chapter focussed on object deposition in natural places only. However, this was not the only field of practice where metalwork was deposited. Metal items figured in the burial ritual as well. This chapter will be devoted to this particular practice, thus serving as an important addition to the findings of the last chapter.

Although the urnfields from the southern Netherlands have received ample attention of old, the bronzes found in burials have generally been neglected (see Tol 2000b for an exception). The deposition of objects into a grave, however, raises significant questions on the nature of the urnfield burial ritual in our region. Some of these are fundamental to the present research. We shall focus on the following questions:

- What was this deposition of metalwork in graves? How frequently and at which stages of the burial ritual did it take place, and which objects were used?
- What did the deposition of burial gifts mean? Do graves containing metalwork contrast with other graves, and does this provide clues on gender and social roles of the individuals buried with metalwork?
- In what way does the deposition of metalwork in graves contrast with the deposition of metalwork in natural places that was described in the previous chapter?

9.2 DISCUSSION OF THE AVAILABLE EVIDENCE

Unfortunately, there is at present no complete catalogue of all urnfields from the southern Netherlands. In a recent survey, Roymans (1991) counted 371 urnfields from the region, 85 of which date to the Late Bronze Age only (fig. 9.1). An overview of these urnfields has been published by Gerritsen (2001). From the latter publications, it becomes clear that among these 371 urnfields there are urnfields from which no more than a few urns survive and urnfields that have been excavated almost completely. Among the not or only superficially published urnfields, there are important ones like the large urnfield of Weert-Boshoverheide (Bloemers 1988), Neerharen-Rekem (De Boe 1986; Temmerman 2002; Van Impe 1980b) and several from Wijchen (unpublished). Even if urnfields have been published, the often crude excavation methods of earlier generations make it likely that not all of the often insignificant and breakable bronze items

have survived. In this study, some 268 burials with metalwork/or green discolourations on bone from probably 61 urnfields all over the region were assembled, ranging from the Late Bronze Age to the beginning of the Middle Iron Age (appendices 7.3 and 7.4).¹ The discussion will focus on the developments up until the Ha C phase (until c. 600 BC). Some urnfields (Haps, Nijmegen-Kops Plateau, Someren) contain rich graves of the later Ha D/La Tène A phases (graves with iron spearheads). These are listed here when they are present in the urnfields studied, but excluded from further discussion (see Ball 1999; Fontijn 1996; Roymans 1991). Modern, reliable physical-anthropological analyses of cremation remains from the Netherlands are available only for the Dutch Early Iron Age urnfields. Cremation remains from Belgian urnfields were analysed in the 1960s and 1970s but are now generally considered suspect (personal comment B. Temmerman). The lists in appendix 7.3 and 7.14 include bones with green discolourations as well, but since we are at present unable to see whether these are really the result of bronze grave gifts, they are included in the discussion on bronze deposition (see the discussion 7.13.3). This survey does not pretend to present a complete overview of the entire evidence on metalwork finds, but I assume that it covers the most general find categories.

9.3 THE URNFIELD BURIAL RITUAL AND THE PROVISION OF ARTEFACTS

Before dealing with the metalwork finds from graves, it is necessary to pay some attention to the urnfield burial ritual as a whole.

The urnfield burial ritual has three important characteristics. First, cremation of the body has become the most important way of treating the body of the deceased before interment. Second, the larger part of the community was buried in a collective cemetery, the urnfield, including both sexes and all ages, with the possible exclusion of new-born babies (Fokkens 1997). Since most were interred in an individual grave, often underneath a moundlet, and cemeteries were in use for centuries on, large urnfields developed. Estimation of population sizes for both Late Bronze Age and Early Iron Age urnfields suggests that the average urnfield is the burial ground of a relatively small community consisting

of 10 to 20 people, three or four farms (Fokkens 1997 and references cited therein). Third, many urnfields display a variety of burial monuments: flat graves, long barrows (Dutch: *langbedden*), and those enclosed by circular and rectangular ring-ditches. Only for the Early Iron Age, there is evidence for graves that contrast with others by their monumentality: the large long barrows of type Someren (Kortlang 1999), and the large circular mounds that cover the Ha C chieftains' graves (Roymans 1991).

After cremation, part of the cremated remains were collected from the pyre, and deposited in a shroud or urn. For all urnfields studied, far less than half of the burials in an urnfield contained artefacts. Most frequent are small pots or cups, the function of which is unclear: they may have contained food or drink, or oils that were poured out over the body before cremation. The largest number of such small pots recorded so far is in the large urnfield of Best (in 23 % of the preserved graves) and the small one from Maastricht (26 %). Bronzes clearly are the second-most deposited artefact. As table 9.1 shows, the frequencies of bronzes range from 19 % of the recovered burials to no bronze at all. This table is based on urnfields that yielded relatively large numbers of intact graves, and were almost completely excavated.² It is clear that metalwork items in urnfield graves are the exception rather than the rule. The single exception seems to be the (unpublished) Early Iron Age urnfield of Neerharen-Rekem, where almost any grave contains metalwork (Temmerman 2002). But as Temmerman's own survey of Belgian urnfields indicates, this cemetery is clearly

exceptional, and low frequencies like those shown in table 9.1 are the norm (Temmerman 2000, 84). Much rarer than bronzes are artefacts of iron and gold, stone, glass and flint. I have not carried out an exhaustive survey of the non-metal find categories, but their frequencies can be estimated at 5 % or lower. Iron objects are only known from Early Iron Age urnfields. Figure 9.8 shows that iron objects gradually replaced bronze ones, with iron becoming dominant only in the Middle Iron Age. As can be seen in the appendix 7.3 and 7.4, the metalwork items are generally ornaments and this also applies to the majority of the stone and glass objects.

9.4 ORNAMENTS AND TOILET ARTICLES IN URNFIELD GRAVES

For the Late Bronze Age and Early Iron Age (Ha A2 until Ha C), the most recurrent metal ornament type are pins, followed by bracelets/arm rings, some of which are twisted, and some decorated. Also known are pendants and gilded rings (particularly from Early Iron Age context), spirals in different sizes and of different shapes, among them *Brillspiraal* (Early Iron Age), bronze beads, and a few razors and tweezers. From Early Iron Age burials, there is evidence for pins and small rings carried out in iron instead of bronze. The material from these burials is often damaged by the cremation fire, and this makes many artefacts difficult to recognize.

Pins

Pins are not only the most recurrent artefact; they are also the ornament type that shows most variation in form. They

Site	Date	Graves	Bronze	%	Iron	%	Pots	%	References
Hilvarenbeek-Laa Spul	LBA	67	3 (3)	4	-	0	8 (8)	12	Verwers 1975
Knegsel-Knegsels Heide	LBA(EIA)	63	3(2)	3	-	0	?(>2)	-	Braat 1936
Ranst-Ranstveld	LBA	25	5(4)	16	-	0	5(4)	16	Lauwers/Van Impe 1980
Bergeijk-Witrijt	LBA/EIA	23	2(2)	9	-	0	4 (3)	13	Van Giffen 1937
Best-Aarlesche Heide	LBA/EIA	44	18(8)	18	-	0	9(9)	23	Willems 1935
Donk	LBA/EIA	142	12(10)	7	2(2)	1	26(25)	18	Van Impe 1980
Esch	LBA/EIA	26	-	0	-	0	2(2)	8	Van den Hurk 1980
Goirle	LBA/EIA	49	2 (2)	4	1	2	3	6	Verwers 1996a of b
Nijmegen-Kops Plateau	LBA/MIA	38	5 (5)	13	20 (8)	21	2 (2)	3	Fontijn 1995
St.Oedenrode-Haagakkers	LBA/EIA	41	17 (5)	12	-	0	1(1)	2	Van der Sanden 1981
Valkenswaard-Het Gegraaf	LBA/EIA	99	2	2	-	0	1	1	Brunsting/Verwers 1975
Venlo-De Hamert	EIA	94	9 (9)	10	-	0	19(19)	20	Holwerda n.d.
Beegden	EIA	19	-	0	1	5	-	0	Roymans 1999
Someren-Waterdael	EIA	72	-	0	6(3)	4	-	0	Kortlang 1999
Mierlo-Hout-Snippenscheut	EIA	49	1	2	2(2)	4	2(2)*	4	Tol 1999
Wijk bij Duurstede-De Horden	EIA	73	5(5)	7	1	1	-	0	Hessing 1989
Roermond-Musschenberg	EIA	139	35(27)	19	7(7)	5	13(12)	9	Schabbink/Tol 2000
Sittard-Hoogveld	EIA	91	1	1	1	1	11(11)	12	Tol 2000
Maastricht-Vroendaal	EIA	15	0	0	-	0	4(4)	26	Dijkman/Hulst 2000

Table 9.1 The frequency of bronze and iron objects within urnfields. Only those graves are included in which there is a possibility that grave gifts could have been preserved.

can be roll, vase, convex or biconical-headed (fig. 9.2). Pins with ribbed heads are also known, as are a few pins with decorated shaft. Although clearly meant to be seen, these pins are generally less conspicuous than most pins from the Middle Bronze Age B. They are generally interpreted as dress-fasteners as they generally seem to be too long to serve as hair pins. A pin from Neerpelt-Achelse Dijk (Belgium) is more likely to have been used as a fastener for a shroud than as an ornament (Van Impe 1995/1996, 30). It is unclear whether we are dealing with locally-made or imported objects. Most pin-types mentioned are known from more than one region (England, Belgium, northern France; O'Connor 1980, list 179, 181, 184, 185, 189). Nevertheless, these are all easy-to-make objects of a rather simple form, and it is likely that they were produced locally.



Figure 9.2 Fragments of pins from the Weert-Boshoverheide urnfield, coll. M. Heijmans: unit 'E' (scale 1:1).

Bracelets and other rings

Next in line are all sorts of rings. In view of their sizes, most have been used as bracelets, or as arm rings (fig. 9.3). Rings with a much smaller diameter are also known (fig. 9.4). Small rings have occasionally been interpreted as finger rings (Weert; Felix 1945, no. 451), but often the diameter of these rings seems either too large or too small for such a purpose (Hessing 1989; Wijk bij Duurstede, grave no 26). Some small rings may be interpreted as horse-gear (for examples:



Figure 9.3 Twisted bracelet from the Weert-Boshoverheide urnfield, coll. J.H. and P.M. Houben, no. 294 (scale 1:1).



Figure 9.4 Set of small rings from the Weert-Boshoverheide urnfield, coll. M. Heijmans: unit 'C' (scale 1:1).

fig. 9.4). With regard to the objects for which an interpretation as bracelet or arm ring seems most likely, it can be concluded that these objects are plain and very simple, without clear elements of display or decoration. They are sometimes twisted (fig. 9.3), and an occasional one has slightly everted terminals (Venlo-De Hamert no. 35). They are probably regional products. Occasionally, lavishly decorated bracelets are found, like the one from Neerharen-Rekem with its geometrical decoration (fig. 9.5, De Boe 1986). For this type of decoration, the only parallel known is a bracelet that was recently dredged up from the river Meuse near Lith (chapter 8). Exceptional are the penannular gilded rings, known from a few urnfields (O'Connor 1980, 215). These are rings of base metal covered with gold sheet. Their function is not clear: they seem to be too small to have served as bracelets. A fragment of a ring entirely made of gold comes from an Early Iron Age grave from Nijmegen-Kops Plateau (burial no. 88), and from Borsbeek where a fragment of a gold plate, a bronze bracelet fragment, and a small cup accompanied the gilded ring in grave 10 (Warmenbol 1988, 256). Gilded rings are dated to the Early Iron Age, or around the transition to this period and are seen as imports from beyond the region, probably Ireland or Britain, although north French examples are also known (O'Connor 1980, 215; Warmenbol 1988, 255). Warmenbol (1988, 255-8) has shown that these gilded rings are all from the richer graves, and are clearly exceptions among the general inconspicuous nature of most bronze rings and bracelets.

Spirals

It is hard to say something more on the variety of *spirals* recovered from burials. They are generally incomplete, and due to their fragile nature more damaged than other artefacts. The *Brillspiral* fragment from Roermond-Mussenberg grave no. 34 probably served as a brooch or belt ornament (cf. Verlaeck 1996, 28).




Figure 9.5 Decorated bracelet from the Neerharen-Rekem urnfield. Object drawing based on De Boe 1986.

Pendants, necklaces and head dress

A number of bronze ornaments were probably used as pendants. This is most clear for the small conical objects that have repeatedly been found in urnfields in the Kempen (both in the Dutch and in the Belgian part). A number of graves contained several of such objects, ranging up to 15 (Luijksgestel; fig. 9.6). To find the same type of object in such quantities is highly unusual for urnfield graves (cf appendix 7.3 and 7.4). It has been argued that these pendants were part of necklaces (fig. 9.7), placed on the body before cremation. Apart from a stray find (Cuijk) and one such pendant from a grave in Roermond-Mussenberg (no. 34), they are only known from urnfields situated in the Kempen (Best, Luijksgestel, Overpelt-Kruiskiezel, Achel-Pastoorbos, Neerpelt-Roosen). Associated finds date them predominantly to the Early Iron Age. A burial from the Meerhout urnfield (no. 7) also contained one comparable conical pendant. This burial may date from the Late Bronze Age as well. Such objects are unknown from other regions, and even in the southern Netherlands they are restricted to a small micro-region. We must be dealing here with locally-specific dress items. Some small socketed spirals, bronze and glass beads, and an occasional stone perforated amulet (Knegsel; Braat 1936, fig. 31) are examples of other types of pendants. This category includes some non-bronze ornaments as well. For all the pendants we are probably dealing with



Figure 9.6 Burnt conical pendants from the Luijksgestel urnfield (scale 1:2).

remains of necklaces, although some can also have been tied to garments. An observation done by Van der Sanden made clear that there were alternative ways to decorate the body: he found seven small round bronze objects in one grave, one of which was attached to what probably was a skull fragment (St.-Oedenrode, grave 13a: Van der Sanden 1981: grave 13a). We might be dealing here with bronzes being part of some sort of head dress.

Razors and tweezers

Finally, in a few burials razors and tweezers have been found. These are generally seen as implements to adorn the male body (Treherne 1995). Three razors have a V-shaped notch and two of these also have a circular perforation in the centre of the blade. O'Connor has termed such razors 'Dutch bifid razors'. Warmenbol (1988, 252-5), however, has argued that




Figure 9.7 Reconstruction of the way in which the conical pendants might have been worn.

they are not so exclusively 'Dutch', but have good parallels in razors of the Havré group, mainly distributed over Britain and Belgium. The few tweezers known have an undiagnostic form. Associated finds (Goirle) date such razors to the Early Iron Age rather than the Late Bronze Age. O'Connor (1980, 219) considers the Deurne razor as an argument for an Ha B date, but the association between the pottery preserved from

this urnfield and this particular find is far from certain. Like gilded rings, razors and tweezers often come from the richer graves, but unlike Bronze Age warrior graves, which often contain tweezers or razors, these are not associated with weaponry (cf. Treherne 1995).

Conclusion

Summarizing, the following conclusions can be drawn. Ornaments deposited in urnfield graves are predominantly made of bronze. Only in the category of pendants do other materials figure. Urnfields from the Early Iron Age are known in larger quantities than Late Bronze Age ones. Therefore, the observation that pendants are predominantly known from the Early Iron Age does not necessarily indicate a change in the way the dead were dressed. Apart from pendants and the presence of iron ornaments (pins), there are no fundamental differences between Late Bronze Age and Early Iron Age metal ornaments. Ornaments are first and foremost pins and bracelets. As a rule, most objects are simple, plain ones, not lavishly decorated. It is therefore likely that most were made in the southern Netherlands itself. Conical pendants are the clearest examples of local products. Objects like the lavishly decorated bracelet from Neerharen-Rekem (fig. 9.5) or the gilded and golden rings may be imports, but these constitute a clear minority.

9.5 DEPOSITION OF WEAPONRY

Other metal artefacts than ornaments and dress fittings are rarely found in burials. The most conspicuous exception are the prestigious sword graves from the Early Iron Age, which can be shown to be a burial equipment in their own right. These are the ones with Gündlingen swords (Gündlingen phase), and the later so-called Ha C 'chieftains' graves'. Other weapon graves are unknown, apart from a burnt spearhead and burnt flint arrowheads in the Donk urnfield (nos. 35 and 44 respectively; appendix 7.4), and a spearhead from Weert-Boshoeverheide (no find association recorded). The finds from Donk are most likely to date from the Early Iron Age rather than from the Late Bronze Age.

Gündlingen weapon graves

Gündlingen swords have already been described in the previous chapter (section 8.5.5; fig. 8.14; appendix 5.5). These swords were carried out in bronze but there are iron of comparable form and style as well. Both were deposited in rivers as well as in burials. The southern Netherlands have yielded evidence of probably seven burial finds. It is remarkable that in two cases (Weert-Boshoeverheide and Neerharen-Rekem) we are dealing with graves with a clear collective element. In Weert fragments of swords seem to have been found in three barrows, one of which was quite large (tumulus O; Gerdson 1986, 168). Tumulus O contained six individual graves, three




Figure 9.8 The relative frequency of bronze versus iron objects in different urnfield graves. (Venlo = Venlo-De Hamert). For the datings of the different urnfields see appendix 7.3 and 7.4.

of which were buried in extraordinary large urns. The urn from which the four fragments of a sword came was 45 cm high and 133 cm wide. In Neerharen-Rekem, three bronze spears and swords with two chapes were deposited in one grave (no. 72) which is said to have contained the remains of three individuals. In both Weert and Neerharen-Rekem we thus seem to be dealing with graves that are non-normative. There are examples of double burials in one grave, and in Beegden no. 22 the remains of no less than seven individuals seem to have been buried. A look at appendix 7.3, however, indicates that such multiple-burials are the exception rather than the rule. The Weert and Neerharen-Rekem graves as therefore not only exceptional for their grave gifts, but also because they are collective graves, whereas the majority of urnfield barrows are individual ones. In Maastricht-Vroenhof another Gündlingen sword was found. It is less clear whether the sword found was related to a grave of the nearby urnfield. Both the Weert and Neerharen-Rekem finds were broken/burnt and deliberately damaged. The weapon sets (sword-spearhead, or just a sword) do not basically differ from earlier ones encountered in hoards like the Overloon (Middle Bronze Age A) or Escharen (Middle Bronze Age B) hoard.³

Ha C 'chieftains' graves'

The designation 'chieftains' graves' is commonly used to refer to a group of graves in which iron (Mindelheim) swords were deposited, often together with prestige goods from the Hallstatt area: wagon parts (linch-pins, yokes), bronze vessels, and horse-gear (chapter 8, section 8.5.6; Roymans 1991). Besides these artefacts, it is also the size of the graves that sets them apart from others. Among these graves are the most monumental ones ever encountered in our region.

Like their bronze predecessors, the swords were also imported from far away, but this time probably from continental regions only (chapter 8). The sword from Oss, for example, was probably produced in southern Germany (Roymans 1991, 36). Among the differentiated group of graves with iron Hallstatt swords, a few graves stand out because of their burial sets. These contain elements of a four-wheeled wagon, a yoke, horse-gear, (bronze or iron) axes, and a bronze situla imported from central Europe. In the case of the bronze vessel, the wagon and the horse-gear, we are clearly dealing with categories of objects that have no precedents in the Bronze Age material culture of the region

(see the previous chapter and Roymans 1991, 59). Wijchen and Oss in particular are rich beyond comparison, and the monumental size of the Oss grave (diam. 52 m) testifies to its elite character, hence the designation ‘chieftains’ graves’. The horse-gear and wagon parts should probably be seen as related: draught animals for the four-wheeled wagon. The use of such wagons, with the lavishly decorated linch-pins, is generally seen as ceremonial; they are unsuitable as true chariots (Pare 1991a: chapter 12). It has been suggested that such wagons relate to ideas about the journey of the deceased to the after-world (Roymans 1991, 202). What is important here, is that such an elite ideology is unprecedented, and firmly rooted in ideologies of the Hallstatt elites to the south from where these objects must ultimately have been imported. The local elites of the southern Netherlands thus seem to have referred explicitly to a non-local, elite warrior ideology.

The bronze vessels are also unprecedented in our region. In the Hallstatt region itself such vessels are always part of an entire drinking-service set, probably indicating the social significance of drinking bouts (Roymans 1991, 60). In the southern Netherlands, however, they were repeatedly used as urns. Although it is widely recognized that in central Europe hospitality, and hence drinking bouts, formed an integral element of the martial elite ideology (Diepenveen-Jansen 1999; Dietler 1990), this value may have been less important in the chiefly ideal that was constructed in the Dutch chieftains’ graves. At least, it was contextualized in a different way. Only in the Wijchen grave, the bronze vessel seems to have been deposited in a way more in keeping with its original Hallstatt meaning. Roymans (1991, 61) has demonstrated that here fragments of a bronze ribbed bucket were originally deposited in an urn now lost. There are other indigenous traits as well: cremation instead of inhumation, the *pars pro toto* character of the burial (only parts of wagons and horse-gear were deposited), and the deliberate destruction of most swords (compare the different treatment of swords in wet deposits and burials listed in appendices 5.4 and 5.5).

Hallstatt C and the adoption of a new elite ideology

Summarizing, we can say that the Ha C chieftains’ graves for a part linked up with already existing local notions and practices but their basic outline had been adopted from southern Hallstatt elite groups, and contrasted sharply with local ideas current in the burial ritual. We shall come back on this in chapter 11. Illustrating this, fig. 11.4 there shows the categories that are present in an average urnfield burial containing artefacts, in comparison with the categories present in a chieftains’ grave (fig. 11.5). It is conspicuous that in chieftains’ graves there is no evidence at all for the significance of body ornamentation that is so important in general urnfield graves. Even razors or tweezers, which seem

to be essential in Bronze Age warrior graves throughout Europe (Treherne 1995), are no longer present in the Early Iron Age weapon graves (see also Pare 1991a: catalogue).⁴ The small pots repeatedly found in average urnfield burials do not have a counterpart in the chieftains’ graves either. On the other hand, the latter graves contain evidence for entirely new objects in the burial ritual: horse-gear, wagons, and large bronze vessels.

9.6 STAGES IN THE BURIAL RITUAL AND THE INCLUSION OF ARTEFACTS

Above the most current metalwork finds in burials were introduced. We shall now try to make sense of their presence in burials. In order to do this, it is first necessary to find out how they got there. As the general burial ritual involves a complete destruction of the body (cremation), and a second phase in which the ultimate grave assemblage is constructed out of its scarce remains, this is not a redundant question.

Dressing and burning the deceased

The first phase involves placing the dead body on the pyre and leaving it there before the mourners set fire to the pyre. It is very well possible that the deceased was not lying there in his or her everyday clothes, but in a specific dress, with his or her body ornamented for the occasion. Shaving or hair-dressing may have been among the acts carried out (Treherne 1995, 121). There may have been funeral meals on the occasion of the cremation, and objects may have been placed next to the deceased on the pyre, as gifts, as part of a burial equipment. These acts all contribute to the specificity of the event, and to a specific ultimate portrayal of the deceased before he or she disappears from sight. Some of these acts have potential archaeological correlates: clothes will burn completely, but bronze parts of clothing will remain identifiable, although in melted condition, as will parts the meal (animal bones, ceramic vessels thrown into the fire or placed on the pyre). Bronze, stone or flint objects will –although burnt– survive the fire. These burnt objects are termed *cremation artefacts* (Roymans 1990, 219). To what extent bronze objects melt depends on their specific alloy, which is unknown for the material under investigation.

Collecting the burnt remains

The next step involves the collection of objects from the burnt-out pyre, in order to take it to a grave. In most cases, the pyre seems to have been in a different location than the grave where the remains were interred. Picking out human remains from the pyre heap may lead to incomplete retrieval. Interestingly, cremation analysis shows that for the Late Bronze Age and Early Iron Age only a part of the bones that remain after cremation was collected. Clearly, there was no intention to recover as much as possible, to the extent that

a completely recovered urns only contained one gram of bone (Fontijn/Cuijpers 1998/1999, table 2: grave no. 66). Apparently, it was the representative character of the collected remains that counted. The assembled pieces may have been considered as a *pars pro toto*, rather than a full rendering of the individual. The counter-argument, that the incomplete bone assemblages in graves are simply due to the fact that most bones become too small to be retrieved, can be refuted: only in special kilns built for the occasion, where temperatures of 1000 °C (Fontijn/Cuijpers 1998/1999, 53) can be reached, do human bones become no more than dust. There is no evidence that such large kilns could be and were constructed in prehistory. In an open pyre, temperatures hardly exceed 800 °C, and the characteristics of analysed bone are well in keeping with such temperatures (Fontijn/Cuijpers 1998/1999, 53). At such temperatures, cremated bone is deformed and cracked, but still of easily recognizable size. Incomplete collection of remains is therefore the most likely explanation for the underrepresentation of bones in graves, all the more so, as it is also in keeping with a recurrent observation concerning cremation artefacts: objects that can crack and break during heating, like bracelets or large rings, tend to be incomplete as well. Most burnt bracelets I have seen are incomplete. I therefore assume that the same *pars pro toto* attitude prevailed for cremation artefacts.

Adding artefacts to the cremated remains: the final representation of the deceased

The final stage where artefacts were added to the interment is when the collected remains were put in a container or a shroud. In view of their unburnt condition the small pots that are often found among the remains are such post-cremation artefacts, and so are the ceramic and glass beads, stone pendants, and many bronzes. For the latter, however, this is not always clear, since cremation can take place at temperatures that are so low (c. 600 °C) that bronzes do not melt. There are some examples of such low-degree cremations, but these seem to be exceptional. The general white colour of the bones indicates that temperatures were higher as a rule (Fontijn/Cuijpers 1998/1999, 53). At any rate, many bronzes must have been added to the grave contents after cremation had taken place. It is interesting to see that these are sometimes the same objects as presented on the pyre, like pins. This is an argument for the theory that the absence of bronze objects among cremation remains is not simply the result of incomplete recovery from the pyre heap (suggesting that it is well possible that every deceased wore bronze bracelets and so on, but that these were only occasionally recovered from the pyre remains). That objects were added *post*-cremation is an argument in favour of the view that it was apparently significant that the deceased was associated with this bronze object after cremation as well. Nowhere is

this more clear than in the case of tweezers and razors. As can be seen in appendices 7.3 and 7.4, some graves contain such toilet articles. As far as can be judged from the publications, these were never burnt, and therefore probably added to the grave after cremation. In the dressing and decoration of the deceased's body, a razor or tweezer makes some sense. As was remarked earlier, for some well-preserved Middle Bronze Age graves from Denmark it could be shown that the dead were indeed shaven before interment, and that the razor put next to the body still contained beard hairs (Treherne 1995, 121). We might expect the same for our Late Bronze Age/Early Iron Age razor graves. However, adding a razor when the deceased was already transformed into a small heap of bones makes less sense in terms of body treatment, and is more an argument for the theory that the act of shaving or picking out beard hairs (tweezer) had important cultural significance, emphasized in the incorporation of the razor in the final grave. This, of course, might well go together with the actual use of this razor to shave the deceased before his cremation.⁵

Conclusion

Considering the role of artefacts in relation to the stages in the ritual itself, their presence among cremated remains is generally more than the logical result of the fact that the body was decorated and dressed; ornaments and toilet articles were added to the cremated remains as well, implying that they were meaningful to the final representation of the deceased, and indicative of a specific social identity.

9.7 THE DECORATED DEAD

The items that were deposited in burials can all be interpreted in the sphere of the decoration and adornment of the body, and for that reason the objects are prone to be used in the construction and communication of social identities and differences (Sørensen 2000, 124). As set out in chapter 3, we must be dealing with people made to look like *particular kinds of persons*. It is important to realize that the image of personhood thus constructed relates to a highly specific occasion: the moment when the deceased, decorated and dressed, was placed on the pyre, just before the final transformation of his or her body. The deceased's appearance is a costume of death rather than anything else. With regard to post-cremation artefacts, we are again dealing with a special event: the bringing together of the final remains of what was once a living individual before these are hidden from view forever. The addition of body ornaments and toilet articles to a heap of cremated bones is an even better illustration of the symbolic significance of ornaments and personal appearances, for the ornaments were added to the body at a stage when there was no longer any physical appearance left.

If we accept this conclusion, the following question should be asked: since graves with ornaments and dress items are a clear minority, are we perhaps dealing here with a specific selection of people? It may be obvious that we are in a bad position to study such questions: after all, the metalwork fragments are the only surviving elements of what must have been an entire appearance (hair, tattoos, garments and so on). Also, information on the position of the ornaments on the body can be meaningful (Sørensen 2000, 135), but again such information does not survive the cremation process. Actually, only a few aspects of dress and body decoration can be studied archaeologically. Apart from the relative frequency of metal and other objects in urnfields, the presence or absence of ornaments may be related to age and sex. Given the variety of burial monuments, it can also be investigated whether metalwork was related to specific kinds of graves only (like long barrows, flat graves etc.).

Frequency of graves with metalwork

The relative frequency of graves containing metalwork varies considerably, as we saw earlier (table 9.1). Compare, for example, the Early Iron Age cemeteries of Mierlo-Hout and Roermond. From the 49 surviving interments in Mierlo-Hout, only one contained bronze, and two iron contained objects. Here, the urnfield was used for centuries, but bronze metal objects hardly seem to have played a role in the burial ritual. In the contemporary urnfield of Roermond, however, 19 % of the graves contained bronze objects. Although still a minority, this is more in line with a situation in which at least one deceased in every generation was burnt with metal body ornaments. On the other hand, even in the most metal-rich urnfields, such graves are a minority. It was already argued that this cannot be explained entirely by careless selection after the cremation alone; it was also a minority of the deceased that carried such ornaments.

The relation between type of burial monument and provision of metalwork in the grave

In urnfields where a variation of grave types exists, it appears that bronze-equipped graves are known from all sorts of graves. Only in the case of the Early Iron Age equipment with clear Ha C links, it is clear that these objects tend to come from large, monumental, round barrows (Oss, Horst, Baarlo).

The relation between the presence of metalwork and the age and sex of the deceased

The collected evidence does not show a straightforward pattern between the presence of metal in graves and certain sex/age categories (appendices 7.4 and 7.5). Both adults and children, and males and females alike were buried with bronze and iron goods. In general, however, adult graves predominate, and this indicates that in general adults carried

metal ornaments. This implies that such objects were at least related to individuals who had reached a certain, culturally meaningful, stage of life. But the pattern is far from clear. If we focus on the data from individual urnfields only, then it can be seen that in some urnfields both children and adults carry metal (Roermond for example), but that in others it seems to have been reserved for adults only (e.g. Weert-Raak).

With regard to sex we see the same. In general, more females had metal objects than males, but again the pattern is not unequivocal⁶ (table 7.4). If we go down to the level of the individual urnfield, there are patterns, however. In Roermond, when sex is known, the (adult) deceased almost all appear to be females. In other cemeteries, however, we find both male and female graves containing metal objects. As suggested for age, the impression is again that the use of metal objects in graves differs between the individual urnfields (and consequently between the local groups these represent).

Conclusion: the meanings of body decoration as a local, idiosyncratic phenomenon

The available evidence does not suggest that pins, bracelets and rings in general had a fixed sex/age-specific meaning, in the sense of meanings shared by the different local groups in the southern Netherlands. The conclusion should be *that metal ornaments were used to express different ideas from group to group, and time to time*. This is not a negative conclusion! Rather, it seems to say something about the relative autonomous expression of ideas at the level of the local urnfield group itself.

Focussing on the level of the individual urnfield, what can be said about the meanings of ornaments in graves? Take for example the relatively metal-rich urnfield of Roermond. It is clear that most graves with bronze objects belong to females. Only one male grave has a fragment of a bronze bracelet, and this is quite an extraordinary grave in the entire urnfield because of its large ring-ditch (diameter 16). Among the female bronze-equipped graves, there are differences, however. No. 1, for example, contains spiral ornaments (pendants?) and a ring. The female from no. 39, however, was probably burnt wearing a bracelet and an earring. What may have happened here is that the attempt was not so much to differentiate women from men, but rather *to treat women in terms of differences among themselves*. After all, most women lack body ornaments, and among those with ornaments, the objects themselves are different. Sørensen (2000, 139-40) has observed a similar phenomenon from much better data for Middle Bronze Age graves from southern Germany. We can only speculate as to what motivated people to make such a differentiation between women. With the theory on the significance of personhood in mind, it might be ventured that it related to the achievement of particular life stages.

Sørensen (2000, 139) argues that such creations of different types of women was probably based on gender identities such as 'distinctions made due to physical or 'moral' development, reproduction or 'marriage'-like contracts'. In theory, similar differentiations might be brought out elsewhere by other means that are elusive to us (by garments alone for example). In other urnfields graves containing bronzes are from males only (appendix 7.4: Someren-Waterdael; Weert-Raak; Sittard-Hoogveld), or from both adults and young individuals (appendix 7.4: St.-Oedenrode; Wijk bij Duurstede).

9.8 LOCAL AND SUPRA-LOCAL PERSONAL IDENTITIES

The use of objects in the construction of personal identities in graves was not entirely shaped in an idiosyncratic, local fashion. There are examples of conventions shared between different local groups as well. Evidence was found for shared ideas on two levels. The first is the use of a common, female dress, specific to a micro-region within the southern Netherlands. The second concerns a specific male warrior identity, that has clear and deliberate references to elite ideologies that were shared between entire regions.

Female identities that were shared among adjacent local groups

The above findings have so far pointed to the ambiguous and non-fixed meanings of pins, bracelets and rings in terms of sex and age. If the cremation analyses can be trusted, this seems less valid in the case of the conical pendants: the investigators argued that these are all from the graves of females (fig. 9.6 and 9.7). Three of the analysed specimens are from the same urnfield (Neerpelt-Roosen), one is from another, situated nearby. These objects stand out for other reasons as well: they are of a form typical for one area in the southern Netherlands only. Moreover, the conical pendants are in most cases not single goods; burials generally contain several of them. Clearly, the deceased had an entire necklace of such pendants. In this sense they are unique, and such bronze-ornamented necklaces can without any problem be termed 'lavish' among the general finds of urnfield graves in general, and, more specifically, with regard to finds of bronze pendants in a grave. There are more finds of such necklaces with several conical pendants; these are all from each other's vicinity, situated in the Kempen around the present Dutch-Belgian border: Best, Luijksgestel, Overpelt-Kruiskiezel, Achel-Pastoorbos, Neerpelt-Roosen. Outside that region I found two examples, one a stray find (Cuijk), the other a single pendant from the Roermond urnfield.

We are dealing here with necklaces that are typical for a small area. On the basis of the existing cremation analyses it seems to have been part of a specific female costume, that had a shared meaning in this area. That the bronze-rich necklaces were part of the dress of a deceased in more than one urnfield is intriguing. Again, we are in no position to

arrive at a real answer, but what these finds make clear is the attempt of the mourners to adorn the body of a specific deceased woman with local products in a way only attested for a small number of neighbouring communities. Such a local, but shared, dress may reflect strong inter-communal ties and a feeling of identity. In practice, it may have come down to existing ties in the field of exchange of marriage partners for example, and the pivotal role of some women therein (in terms of their role of negotiators and/or object of exchange). In contrast with the highly idiosyncratic use of other ornaments, we seem to be dealing here with an example in which the use of ornaments in graves built on a shared understanding of a particular kind of personhood and female identity. Undoubtedly, there are similar examples for other object types with similar roles. In particular we could think of another rich grave set in which the gilded rings are the most conspicuous element. Like conical pendants, these are also repeatedly found in a number of adjacent urnfields, but further data on sex and age of the cremation remains associated with these objects is lacking so far.

Ha C warrior graves and their references to non-local, 'imagined' communities

In the case of the conical pendants, we might be dealing with the female identities that were shared among local groups. They were typical products for the micro-region of De Kempen and were not current in the entire region, let alone beyond. This does not apply to the male warrior burial sets we find in the Early Iron Age Ha C chieftains' graves. The categories in the burial set are similar among different regions ranging from central Europe to the Netherlands (Pare 1991a). They refer to a highly specific elite ideology non-native in our region, on the deposition of parts of ceremonial wagons with draught animals and bronze vessels (drinking bouts) (Roymans 1991). Elements characteristic for European Bronze Age warrior appearances no longer play a role in the new warrior graves at all (sword-spear combinations, toilet articles and body ornaments), which underscores this deliberate otherness. The large dimensions of some of the burial monuments underline that these non-local, supra-regional identities are equivalent to elite identities (Roymans 1991, table 4). Throughout this book, we have seen different examples of the construction of identities that were clearly similar to those of other regions, starting off with the Bell Beaker burial set (chapter 5). It was argued that persons were conceptualised with references to non-local, imagined elite communities, and the Ha C graves involved here would perfectly fit in such a view. In most cases, these identities were male warrior identities. The Ha C graves seem to be the most outspoken argument that such identities were primarily chiefly ones, as these are the only examples

where such warrior identities were constructed on more than one occasion in an individual grave of true monumental size.

9.9 CONCLUSIONS

With regard to the questions posed in the introduction to this chapter, the following conclusions can now be drawn.

The low frequency of object deposition in burials

Although artefacts from burials are known from the Late Bronze Age and Early Iron Age in much larger quantities than before, still only a small number of graves was provided with them. They are predominantly small pots, followed by bronze items and, in the Early Iron Age, by iron ones. The majority of the bronzes are plain, simple items that were probably made locally. Golden, glass and stone objects are also known, but in much lower frequencies.

Ornaments and dress fittings: costumes of the dead before and after cremation

The metalwork and glass, gold and stone objects are in the first place body ornaments (bracelets, rings, pendants for necklaces), dress fittings (pins) and toilet articles. In the Early Iron Age, bronze and iron swords were also deposited in graves, the latter sometimes in association with elements of wagons, horse-gear and bronze vessels (the Ha C 'chieftains' graves'). Metalwork was both part of the death costume of the deceased on the pyre, as well as added to the remains after the cremation had taken place.

Burial goods and the construction of personhood in graves

It was argued that the metal ornaments, pins and toilet articles were instrumental in the construction of personhood. The precise meaning of these appearances escape us, but there are indications that they sometimes served to make differentiations between particular kinds of females. In general, the meanings of the 'decorated dead' seem to have been idiosyncratic to the local group only, since their age and sex associations differ from place to place. Shared conventions on the representations of specific female identities have only been recognized at the level of a micro-region (the conical pendants as a typical dress for the Kempen), but not for the entire region, let alone the supra-regional level. The contrary is true for the male identities that were constructed in the Early Iron Age warrior graves. Particularly in the case of the 'chieftains' graves', deliberate references are made to a non-local, central European ideology.

Selections: ornaments placed in burials versus those placed in natural places

In the Late Bronze Age, bronze ornaments and dress fittings were also deposited outside burials: in rivers and multiple-

object hoards. Although there are types that figure both in graves and in rivers/hoards, like some ornaments, pins and Gündlingen swords, there are differences as well. Among the deposits from natural places there are finds that are clearly absent in urnfield burials: high quality, non-local ornaments, sometimes even of a ceremonial nature (chapter 8: female ornaments in Plainseau hoards, *Bombenkopfnadel* and male warrior identities). For the Late Bronze Age, selective deposition thus seems to have been practised to the effect that items associated with non-local appearances, related to both male and female social roles, were kept out of urnfields. This situation changes entirely in the urnfields of the Early Iron Age, with the new, non-local elite ideology displayed in the 'chieftains' graves'. Here, there seems to be no longer a female counterpart, however.

notes

1 For badly documented urnfields like Deurne St. Josephs parochie or Weert Boshoverheide, individual find numbers are counted as belonging to one individual grave. Whether this reflects a prehistoric reality can no longer be inferred.

2 Van Ginkel (1982) and Tol (2000) published more or less similar tables, based on a smaller but overlapping number of urnfields. There are slight differences between the percentages published there and mine. Reason for this is that I only counted those graves where metal objects could potentially have been preserved. Ring-ditches where the central interment is missing are excluded. In Mierlo-Hout, for example, 165 grave monuments were observed, but only 49 contained remains of the interment. Furthermore, there is uncertainty about the data of old excavations: was every pot published as 'urn' really a container of cremated remains? In Best we are dealing with excavated remains, and therefore I assume that pots described as 'urns' were indeed used as such. In Valkenswaard and Goirle, I also included 'urns' from older and low-quality excavations. There is a risk that small bronze finds from these urns have not generally been recorded. The problems with the older excavations are, however, counterbalanced by the better data of the recent ones, which do not show basically different frequencies of metalwork.

3 Only in the case of Neerharen-Rekem have the cremation remains been analysed. These are interpreted as those of two males and one female (Van Impe 1980b: no. 72). Three individuals in combination with three swords would suggest that we have an argument to suppose that sword-bearers were not just males, as is generally assumed, but include females as well. However, the reliability of the physical-anthropological analyses carried out here has recently been questioned, so we had better not use them in the discussion.

4 It should be remarked, however, that a badly preserved iron blade from the chieftain's grave of Oss, traditionally interpreted as a knife, may also be interpreted as a razor blade.

5 Some metal objects may then also relate to the fastening of a (hypothetical) shroud into which remains were collected. Van Impe claims that the position of a bronze pin in the urnfield of Neerpelt-Achelse Dijk (grave no. 20) indicates that it was used as some sort of shroud fastening (Van Impe 1995/96, 30). The fact that

many pins were found in urns can taken as an argument that most pins were something else than shroud fasteners. When an urn is used, a shroud seems unnecessary, unless cremation remains were always first collected in shrouds and later put into an urn. Even then, the presence of many burnt pins implies that pins as a category were as a rule used for other purposes.

6 There are too few data on iron finds to investigate whether iron was a sex-specific metal. I treat iron and bronze together here.