



Universiteit
Leiden
The Netherlands

Detection of carbon monoxide in the high-resolution day-side spectrum of the exoplanet HD 189733b

Kok, R.; Brogi, M.; Snellen, I.A.G.; Birkby, J.L.; Albrecht, S.; Mooij, E. de

Citation

Kok, R., Brogi, M., Snellen, I. A. G., Birkby, J. L., Albrecht, S., & Mooij, E. de. (2013). Detection of carbon monoxide in the high-resolution day-side spectrum of the exoplanet HD 189733b. *Astronomy & Astrophysics*, 554, A82. doi:10.1051/0004-6361/201321381

Version: Not Applicable (or Unknown)

License: [Leiden University Non-exclusive license](#)

Downloaded from: <https://hdl.handle.net/1887/59009>

Note: To cite this publication please use the final published version (if applicable).

Detection of carbon monoxide in the high-resolution day-side spectrum of the exoplanet HD 189733b[★]

R. J. de Kok¹, M. Brogi², I. A. G. Snellen², J. Birkby², S. Albrecht³, and E. J. W. de Mooij⁴

¹ SRON Netherlands Institute for Space Research, Sorbonnelaan 2, 3584 CA Utrecht, The Netherlands
e-mail: R. J. de Kok@sron.nl

² Leiden Observatory, Leiden University, Postbus 9513, 2300 RA Leiden, The Netherlands

³ Department of Physics, and Kavli Institute for Astrophysics and Space Research, Massachusetts Institute of Technology, Cambridge, Massachusetts 02139, USA

⁴ Department of Astronomy and Astrophysics, University of Toronto, 50 St. George Street, Toronto, Ontario M5S 3H4, Canada

Received 28 February 2013 / Accepted 12 April 2013

ABSTRACT

Context. After many attempts over more than a decade, high-resolution spectroscopy has recently delivered its first detections of molecular absorption in exoplanet atmospheres, both in transmission and thermal emission spectra. Targeting the combined signal from individual lines in molecular bands, these measurements use variations in the planet radial velocity to separate the planet signal from telluric and stellar contaminants.

Aims. We apply high-resolution spectroscopy to probe molecular absorption in the day-side spectrum of the bright transiting hot Jupiter HD 189733b.

Methods. We observed HD 189733b with the CRIRES high-resolution near-infrared spectograph on the Very Large Telescope during three nights, targeting possible absorption from carbon monoxide, water vapour, methane, and carbon dioxide, at 2.0 and 2.3 μm .

Results. We detect a 5- σ absorption signal from CO at a contrast level of $\sim 4.5 \times 10^{-4}$ with respect to the stellar continuum, revealing the planet orbital radial velocity at 154_{-3}^{+4} km s⁻¹. This allows us to solve for the planet and stellar mass in a similar way as for stellar eclipsing binaries, resulting in $M_s = 0.846_{-0.049}^{+0.068} M_\odot$ and $M_p = 1.162_{-0.039}^{+0.058} M_{\text{Jup}}$. No significant absorption is detected from H₂O, CO₂, or CH₄ and we determine upper limits on their line contrasts.

Conclusions. The detection of CO in the day-side spectrum of HD 189733b can be made consistent with the haze layer proposed to explain the optical to near-infrared transmission spectrum if the layer is optically thin at the normal incidence angles probed by our observations, or if the CO abundance is high enough for the CO absorption to originate from above the haze. Our non-detection of CO₂ at 2.0 μm is not inconsistent with the deep CO₂ absorption from low-resolution NICMOS secondary eclipse data in the same wavelength range. If genuine, the absorption would be so strong that it blanks out any planet light completely in this wavelength range, leaving no high-resolution signal to be measured.

Key words. planets and satellites: atmospheres – infrared: planetary systems – methods: data analysis – techniques: spectroscopic – planetary systems

1. Introduction

The extrasolar planet (exoplanet) transiting the K-star HD 189733 is one of the most studied exoplanets to date because the brightness of the system ($V = 7.75$ mag) allows the detailed study of its atmosphere through transit and secondary eclipse measurements. Optical transmission measurements show a steady decrease of the effective planet radius from 0.3 to 1 μm , which is thought to be due to Rayleigh scattering by a high-altitude haze layer (Pont et al. 2008; Sing et al. 2009; Pont et al. 2013). The Rayleigh slope seems only interrupted by an absorption signal from sodium at 0.59 μm (Redfield et al. 2008; Huitson et al. 2012). There is a strong ongoing debate on whether this Rayleigh-scattering signal continues in the near-infrared. Analysis of *Hubble* Space Telescope (HST) NICMOS spectroscopic observations by (Swain et al. 2008) shows absorption signatures from water and methane. However, reanalysis of the same data (Gibson et al. 2011), narrow-band NICMOS observations (Sing et al. 2009), and HST data from

WFC3 (Gibson et al. 2012) show no clear evidence for molecular features and suggest that Rayleigh scattering dominates the transmission spectrum up to 2.5 μm .

Numerous secondary eclipse measurements (e.g. Deming et al. 2006; Grillmair et al. 2008; Charbonneau et al. 2008; Swain et al. 2009) have placed constraints on the day-side temperature structure and trace gas abundances (e.g. Madhusudhan & Seager 2009; Line et al. 2012; Lee et al. 2012). In addition, phase curve observations from the *Spitzer* Space Telescope suggest that the hottest point in the planet atmosphere is shifted with respect to the sub-stellar point, indicating strong longitudinal circulation in the atmosphere (Knutson et al. 2009, 2012). However, several secondary eclipse measurements are also controversial. Swain et al. (2010) claimed to have detected an enormous emission feature at 3.25 μm from ground-based observations, interpreted as non-local thermodynamic equilibrium (LTE) emission from methane. The same team (Waldmann et al. 2012) confirmed this result with new data, in addition to showing similarly strong emission features at 2.3 μm . However, Mandell et al. (2011) saw no sign of the *L*-band emission in NIRSPEC data, with upper limits 40 times lower than the claimed non-LTE methane

[★] Based on observations collected at the European Southern Observatory (186.C-0289).

signal, and suggested that imperfect correction for telluric water is the source of the feature claimed by Swain et al. In any case, the unconventional observation and data analysis performed by Swain et al. and Waldmann et al. needs to be validated with other techniques.

The current measurements of the day-side of HD 189733b were taken at low spectral resolution at best, with most observations taken from broad-band photometry. The limited spectral resolution of the available measurements result in a strong ambiguity in atmospheric composition (e.g. Madhusudhan & Seager 2009; Line et al. 2012; Lee et al. 2012) and temperature structure (Pont et al. 2013).

Recently, high-resolution spectroscopy has delivered its first detections of molecular absorption: carbon monoxide was detected in the transmission spectrum of HD 209458b (Snellen et al. 2010) and in the thermal day-side spectrum of τ Boötis b (Brogi et al. 2012; Rodler et al. 2012). These observations, conducted with the CRYogenic high-resolution InfraRed Echelle Spectrograph (CRIRES Kaeuffl et al. 2004) on the Very Large Telescope (VLT) at a resolution of $R \approx 100\,000$ target the combined signal from individual lines in the CO 2.3 μm molecular band. The strong variation in the planet velocity is used to separate its spectral features from the telluric and stellar contamination. This also allows the determination of the orbital velocity of the planet, and therefore the orbital inclination and true planet mass in the case of non-transiting planets. Recent results from thermal day-side spectroscopy of 51 Pegasi b (Brogi et al. 2013) are somewhat ambiguous. Although the first two nights of data show a combined $\sim 6\text{-}\sigma$ detection from carbon monoxide plus water, no signal was detected on the third night. Although the signal on the third night was expected to be slightly weaker because of the reduced quality of the data and contamination by stellar lines, a complete absence was not expected based on the first two nights. This would mean that either some yet unknown systematics is affecting the data, or that time variability (by e.g. global weather patterns) plays an important role in the atmosphere of this object.

High-resolution spectroscopy has been attempted before for HD 189733 b. Using two nights of Keck/NIRSPEC observations at a resolution of $\sim 25\,000$, Barnes et al. (2010) identified a possible planet signal using a deconvolution method. However, they were unable to make a strong claim because of the low significance of the result. Very recently, Rodler et al. (2013) revisited this dataset and claimed a $\sim 3\text{-}\sigma$ detection of CO lines in HD 189733b.

Here, we present high-resolution CRIRES observations of HD 189733 at 2.0 and 2.3 μm targeting absorption not only from CO, but also from CO₂, H₂O, and CH₄ in the planet's day-side spectrum. Section 2 describes the observations and data analysis and Sect. 3 the cross-correlation procedure used to combine the signal from the individual lines. Section 4 describes the results, which are discussed in Sect. 5.

2. Observations and data analysis

We observed HD 189733b as part of a large programme (ESO programme 186.C-0289, Snellen et al. 2011) to probe molecular signatures in hot Jupiter atmospheres with CRIRES. CRIRES consists of four 1024×512 -pixel Aladdin II detectors, separated by small gaps of roughly 100 pixels. The Multi-Application Curvature Adaptive Optics system (MACAO, Arsenault et al. 2003) was employed to maximise the throughput of the slit. Here, we use data taken during three nights, conducted at two wavelength settings, centred at 2.0 and 2.3 μm . The data were

Table 1. Details of the CRIRES observations.

| Date | λ (μm) | Phase | N | t_{int} (s) |
|--------------|-----------------------------|---------------|-----|----------------------|
| 13 Jul. 2011 | 2.2875–2.3452 | 0.3837–0.4801 | 110 | 13 200 |
| 29 Jul. 2011 | 1.9626–2.0045 | 0.5727–0.6661 | 69 | 13 800 |
| 21 Aug. 2011 | 1.9626–2.0045 | 0.3506–0.4377 | 76 | 12 160 |

Notes. The table shows the observing date, the targeted wavelength range, the planet orbital phase, the number of spectra after background subtraction, and the net integration time.

taken over a planet orbital phase-range near but not during secondary eclipse to maximise the illumination of the planet and the planet's change in radial velocity (see Table 1 for more details). All observations used a 0.2'' slit, resulting in a spectral resolution of $R \approx 100\,000$, and the star was nodded along the slit in an ABBA pattern to subtract the background. The spectra around 2.0 μm contain possible planet lines of H₂O and CO₂, whereas the 2.3 μm region can be used to probe CO, H₂O and CH₄.

On 13 July data were taken with an integration time of 4×15 s per nodding position. On 29 July the integration time was 5×20 s and on 21 August 4×20 s. All three observations spanned roughly 5 h each.

The raw data were flat-fielded, background-subtracted, and optimally extracted using the standard CRIRES pipeline (version 1.11.0). The data from the three nights, for each of the four detectors, were analysed separately. In each case, a $1024 \times N$ matrix was constructed from the N spectra. Bad columns in the matrix (corresponding to certain pixels in the spectra) were identified by taking the standard deviation of each column and finding $>5\text{-}\sigma$ outliers. These bad columns (of the order of 20 per detector) were masked in the rest of the analysis. Further individual bad pixels were replaced by spline-interpolated values.

The next step in the data reduction was to align all spectra onto a common wavelength grid. For this purpose we calculated a template telluric transmission spectrum with water, carbon dioxide and methane lines from HITRAN 2008 (Rothman et al. 2009) using line-by-line calculations with a single model layer and pressures, temperatures, and gas concentrations relevant to Paranal. Since HD 189733A has significant CO lines in its spectrum, we also calculated CO absorption lines at the stellar temperature using HITEMP absorption data (Rothman et al. 2010) and scaled these relative to the telluric lines by comparisons with the data. We then Doppler-shifted the stellar CO lines according to the Earth's velocity, the known stellar systematic velocity, and its planet-induced radial velocity variation (Triaud et al. 2009), and combined them with the telluric spectrum. This was then correlated with each measured spectrum to find the best-fitting second-order polynomial correction on our initial guess of the wavelengths of each pixel, where the polynomial represents a wavelength-dependent shift. Finally, the spectra were spline-interpolated onto a common wavelength grid.

Before we searched for molecular features in the data using the cross-correlation technique, we first needed to remove telluric and stellar signatures. The telluric lines are static in position, but vary in strength due to changes in the geometric airmass and variations in the water vapour content of the atmosphere. The stellar lines are invariable in time to a high level, but slightly change in position during the night due to variations in the radial velocity component of the Paranal observatory with respect to the star (mainly caused by the Earth's rotation).

In this work we analyse the data in a somewhat different way than previously (Snellen et al. 2011; Brogi et al. 2012, 2013) to explore new ways of reducing this type of data. We also performed the analysis with the previous method and found compatible results (see Sect. 4.1). Instead of removing the telluric contamination by fitting the columns in the matrix first with the geometric airmass and subsequently with the residual signals present in the strongest telluric lines, here we used singular value decompositions (SVD, e.g. Kalman 1996). For this we used the algorithm available in IDL. The SVD decomposes a matrix \mathbf{A} into the following matrices:

$$\mathbf{A} = \mathbf{U}\mathbf{W}\mathbf{V}^T, \quad (1)$$

where \mathbf{U} is the matrix of the left singular vectors, \mathbf{W} a (by definition) diagonal matrix of singular values, and \mathbf{V} the matrix of the right singular vectors. In our case the matrix \mathbf{A} represents the array of spectra on a single detector, with the number of pixels and number of spectra as dimensions. The right singular vectors are the eigenvectors and the left singular vectors, scaled by the singular values, indicate how each of the eigenvectors are weighted to form each observed spectrum. A convenient property of the SVD is that matrix \mathbf{A} can be approximated in an optimal way using only the highest few singular values, and setting the lower singular values to zero (e.g. Andrews & Patterson 1975). Here, we reversed this and set the highest singular values to zero to remove the signals that are static with time while affecting the moving planet signal as little as possible. Figure 1 shows an example of a matrix of spectra (detector 2 on the night of 13 July 2011) with progressive subtraction of the singular values for detector 2 at $2.3 \mu\text{m}$. Examples of the left and right singular vectors are shown in Figs. 2 and 3.

The left singular values corresponding to the first two singular values of the $2.3 \mu\text{m}$ data show clear correlations with the signal level in the continuum and the airmass for all four detectors (see Figs. 2 and 4). Hence, the subtraction of the first two singular values is in effect very similar to the first steps used by Snellen et al. (2010) and Brogi et al. (2012, 2013). The third left singular vector is also very similar for all four detectors. Its corresponding eigenvector (Fig. 3) indicates that it is related to shifts and/or broadening of the lines in the spectrum, and its behaviour with time is somewhat similar to parameters relevant to the adaptive optics performance (see Fig. 4). The only parameter in the headers that was similar to the fourth left singular vector is one of the temperature sensors in the instrument. The physical correspondances of these third and fourth left singular vectors is far from conclusive, with correlation coefficients of around 0.5 between these vectors and the quantities plotted in Fig. 4, but it does highlight the diagnostic value of the SVDC for tracking potential systematic effects in the measurements.

As a final step, we divided each column of the array of spectra by the square of the standard deviation. This prevents the cross-correlation analysis from being dominated by very noisy pixels.

3. Correlation analysis

We cross-correlated each reduced spectrum with model spectra of exoplanet atmospheres with Doppler shifts ranging from -200 to $+200 \text{ km s}^{-1}$ relative to the expected planet radial velocity. Orbital parameters of the system were taken from Triaud et al. (2009). To scan the parameter space and check for potential spurious correlation signals, we also performed our calculations for a wide range of amplitudes of the radial velocity




Fig. 1. Example of stellar and telluric signal removal: the array of spectra (in ADU per second) for detector 2 at $2.3 \mu\text{m}$ on 13 July 2011 after setting the first n singular values to zero, with n indicated above the panels.

of the planet, K_p ($50\text{--}200 \text{ km s}^{-1}$). We assumed a circular orbit throughout the paper, which is reasonable given that the highest offset in planet radial velocity for its possible low eccentricity (see Triaud et al. 2009) is lower than the velocity resolution of CRILES.

The model spectra are the result of line-by-line calculations using a range of parameterised pressure-temperature structures (see below), $\text{H}_2\text{--H}_2$ collision-induced absorption (Borysow et al. 2001; Borysow 2002), and absorption from a single trace gas. Line data for the trace gases were taken from HITEMP 2010 for H_2O and CO (Rothman et al. 2010), HITRAN 2008 for CH_4 (Rothman et al. 2009), and HITEMP 1995 for CO_2 (Rothman et al. 1995). A Voigt line-shape was used to calculate the absorption. The atmospheric temperatures at pressures higher than 0.1 bar, where we assumed a temperature of 1350 K, were made to follow the best-fitting temperature profiles of Madhusudhan & Seager (2009), and the temperature at a lower




Fig. 2. First four left singular vectors for all four detectors (black – detector 1; red – detector 2; green – detector 3; blue – detector 4) at $2.3 \mu\text{m}$ on 13 July 2011, divided by their median value. The corresponding eigenvalues for detector 2 are also given to indicate their relative strengths. These vectors can be compared with the parameters in Fig. 4.




Fig. 4. Instrument and environmental parameters possibly related to the left singular vectors plotted in Fig. 2. The median count is for detector 2 at $2.3 \mu\text{m}$ on 13 July 2011, AO Strehl indicates the Strehl ratio from the adaptive optics system in percent, and SV temp is one of the many temperature sensors on the instrument, located at the slit viewer.




Fig. 3. First four right singular vectors, or eigenvectors, for detector 2 at $2.3 \mu\text{m}$ on 13 July 2011.

pressure p_1 was varied from 500 to 1500 K in steps of 500 K. As such, we also included the option of weak thermal inversions at high altitudes. Between 0.1 and p_1 bar a constant lapse rate (i.e. the rate of temperature change with \log pressure) was assumed and p_1 was varied from $10^{-1.5}$ – 10^{-4} in multiplication steps of $10^{0.5}$. At pressures lower than p_1 a uniform temperature was assumed. Volume mixing ratios of the gases ranged from 10^{-6} – 10^{-3} in multiplication steps of $10^{0.5}$.

The correlation analysis was performed for each of the four detectors separately. To combine the correlation signals obtained from different spectra and detectors, we first determined how to weigh their contributions. We did this by inserting an artificial planet signal in the wavelength-aligned data for the system velocity and K_p under consideration, and performed the same data reduction as for the original data. If the data with inserted signal gave a strong increase in correlation value for a particular spectrum, this spectrum was thus expected to give a high signal in the original data as well. Hence, the increase of the correlation when

inserting the artificial planet signal can be used as a weighing factor to favour spectra or detectors for which a stronger signal is expected. The correlation values for each spectrum and detector were multiplied by this increase of correlation, and were added to form the total correlation signal.

In the correlation analysis for CO, there are still some residuals originating from the stellar spectrum. This is not surprising, since the star's radial velocity slightly changes with time due to the Earth's rotation and the star has significant CO lines in its spectrum. Fortunately, the velocities of the planet are at least 20 km s^{-1} offset from that of the star for the observed phases, so the strongest stellar residuals do not affect the correlation signal of the planet. When combining the correlation signals of the different spectra, we masked the velocities that were within 5 km s^{-1} of the stellar velocity after the cross-correlation. Note that this does not significantly affect our cross-correlation signals at the expected planet velocity, but only within the region of the expected stellar signals.

As more singular values are subtracted from the data, parts of the planet signal may also be removed. Hence, there is an optimum number of subtractions that will lead to the best recovery of the planet signal. We tested this effect by again inserting artificial planet signals and evaluating the correlation signal for the different numbers of reduced singular values. Figure 5 illustrates how the planet signal in a single detector first becomes apparent when the stellar and telluric signals are removed, and then slowly disappears as more and more singular values are removed. The slow drop of correlation with more subtracted singular values rises from the fact that there is only very little power in each of these higher singular values. The correlation as a function of number of subtracted singular values is very similar to the correlation of the data without inserted signal, but the correlation values are higher. For each detector, we chose the number of singular values to subtract according to the highest correlation of the inserted signal with respect to the correlation noise, when combined over the entire night. Figure 5 also illustrates what happens to the signal if negative planet signals are inserted. Such a negative signal would correspond to spectra with lines seen in emission instead of absorption.




Fig. 5. Total correlation at the planet position as a function of the number of subtracted singular values for detector 2 at $2.3 \mu\text{m}$ on 13 July 2011 for the planet model giving the highest correlation. Different lines indicate different multiplication factors of the inserted planet signal (see text), as indicated by the labels.




Fig. 6. Combined cross-correlation values for all four detectors as a function of system velocity and K_p . The dashed line indicates where the stellar CO lines are expected to leave the strongest contamination signal. The area in between the dashed lines can also be contaminated by stellar residuals. The dotted lines indicate the system velocity of HD 189733 and the peak position of K_p .

4. Results

Our correlation analysis yields a detection of carbon monoxide at $2.3 \mu\text{m}$, which is presented below. No significant signals are detected for the other bands and molecules, the implications of which are discussed in Sect. 4.2.

4.1. Detection of CO

The cross-correlation assuming different system velocities and values of the planet radial velocity K_p for our best CO template are shown in Fig. 6. The best CO template itself is shown in Fig. 7. A positive correlation value (black) means in this case that the CO lines are apparent in absorption, as in Fig. 7, indicating a non-inverted temperature profile over the probed pressure




Fig. 7. Template spectrum that gives the best correlation value. Note that we are not sensitive to the continuum level of the spectrum. For the sake of clarity, stellar lines are ignored in the calculation of the planet-to-star contrast F_p/F_s . Brackets indicate the wavelength ranges covered by the four detectors.




Fig. 8. Histogram of correlation values outside the expected planet velocity ($+10$ – 400 km s^{-1} with respect to the planet) for detectors 2–4 combined. Error bars are the square root of the number of occurrences in each bin. The dotted line shows a Gaussian fit.

range. The correlation shows a $5.0\text{-}\sigma$ maximum at the expected system velocity, within the range of K_p expected from the measured radial velocity of the star and its estimated mass from spectral modelling (Triaud et al. 2009). The significance was estimated by the peak cross-correlation value divided by the noise in the cross-correlation values in Fig. 6 at system velocities away from the planet signal. The signal is the combination of all four detectors, although detector 1 does not show a clear signal. Note, however, that detector 1 has a low weight, since artificially injected planet spectra give only very faint retrieved signals. This is consistent with the CO spectrum, which shows fewer lines in the wavelength range covered by detector 1.

The observed CO signal is detected at $K_p = 154_{-3}^{+4} \text{ km s}^{-1}$ and $V_{\text{sys}} = -2 \text{ km s}^{-1}$, both consistent with the literature values for the orbital and stellar parameters of the system (Triaud et al. 2009). We estimated the statistical significance of the signal in several ways. First of all, we tested how the distribution of cross-correlation values as calculated for the 110 spectra compare to a Gaussian distribution. A histogram of the correlation values as obtained from detectors 2–4 is shown in Fig. 8. The




Fig. 9. Quantiles of a normal distribution versus the measured quantiles of Fig. 8. The grey line indicates a perfect normal distribution. The two agree well up till the $4\text{-}\sigma$ level, which is determined by the number of available sampling points.

interval of the system velocities over which the histogram was plotted was chosen such that the area of the stellar signal was avoided and a large sample was obtained. The best fit of the histogram to a Gaussian distribution is overplotted, showing a very good agreement. A further analysis of the quantiles of this distribution (Fig. 9) shows that it exhibits no significant deviation from Gaussianity. Only detector 1 shows some non-Gaussian behaviour using the optimal number of singular values, which improved when more singular values were subtracted. Since we did not find a significant signal in this detector and it is weighted very lightly compared to the other detectors, and because the extra singular values effectively only remove very little of the data, the additional subtraction of the singular values had no impact on the final result.

An additional test we performed was the Welch T-test (Welch 1947), comparing the planet signal distribution with the correlation distribution away from the expected planet velocities (see Fig. 10). Unfortunately, we have far fewer spectra available than Brogi et al. (2012, 2013), who performed the same test, so the sampling of the correlations at the planet velocity is poorer here. Nevertheless, we can reject the null-hypothesis that the two samples are drawn from the same distribution at a $4.2\text{-}\sigma$ confidence level.

Our measurements are not sensitive to the continuum level of the planet spectrum because we removed any broadband signal in our data analysis. We are only sensitive to the depths of the narrow absorption lines, which are the parts of the planet spectrum that show the Doppler shift. We determined the line contrast (the depth of the deepest lines with respect to the continuum, divided by the stellar flux) by inserting the model that gives the strongest signal times different (negative) scaling factors (see Sect. 3) until a significance value of $0 \pm 1\sigma$ was reached at the planet velocity for all four detectors combined. The line contrast for the deepest CO lines determined in this way is $(4.5 \pm 0.9) \times 10^{-4}$, which corresponds roughly to the signal from the template spectrum (see Fig. 7). This is the value for the model spectra and does not include the convolution to the instrument resolution. The line contrast including convolution gives a value of $(3.4 \pm 0.7) \times 10^{-4}$. This line contrast can be interpreted as the difference of the line cores with respect to the broadband




Fig. 10. Histogram of correlation values away from the expected planet velocity ($+10\text{--}400\text{ km s}^{-1}$ with respect to the planet), and those at the planet velocity (grey line, scaled), for detectors 2–4 combined.

continuum and can be used as an additional constraint on the temperature profile and CO concentration (see the discussion in Sect. 5). The continuum level will be close to the broadband secondary eclipse depth around $2.3\text{ }\mu\text{m}$ for this transiting planet.

Using the data analysis method we presented previously (Snellen et al. 2010; Brogi et al. 2012, 2013), we found a $4.8\text{-}\sigma$ detection of the CO signal, which is consistent with the results presented here. Hence, either method can be used equally well, although the method presented here is perhaps better founded and allows for a more objective treatment of the data.

4.2. Upper limits for CO_2 , H_2O , and CH_4

In addition to CO, we also searched for signals from H_2O and CH_4 in the $2.3\text{ }\mu\text{m}$ data, and CO_2 and H_2O in the $2.0\text{ }\mu\text{m}$ data, but did not find a significant signal. We determined upper limits of the line contrast by inserting inverted models until a significance value of -3σ was reached at the planet velocity for all four detectors combined. We used the same number of singular values as for the CO analysis. The resulting upper limits of the maximum model (unconvolved) line contrasts is 2.8×10^{-3} for H_2O and 8.3×10^{-4} for CH_4 . The latter is comparable to the value of the medium-resolution secondary eclipse depth of 8×10^{-4} , i.e. the total planet-to-star flux contrast at these wavelengths, as measured with NICMOS on the HST by Swain et al. (2009). Since the continuum level would be close to the medium-resolution planet/star flux contrast, this would imply that the flux in the CH_4 lines would have to drop to zero for them to be detectable at the determined upper limit of the line depth. The contrast of the best-fitting CO lines is $\sim 4.5 \times 10^{-4}$, so CH_4 would have to be significantly more abundant than CO for this to happen, given their similar line strengths in this region. Moreover, the upper atmosphere of HD 189733b would need to be extremely cold (of the order of a few hundred Kelvin). Neither is very likely (see e.g. Madhusudhan & Seager 2009; Moses et al. 2013). Hence, the upper limit on the line contrast of CH_4 does not constrain the abundance in a meaningful way if the measured medium-resolution planet-to-star contrast is correct.

Although we have collected two nights of data at $2.0\text{ }\mu\text{m}$, we were less sensitive to atmospheric signals in this wavelength range due to a combination of more telluric absorption and a weaker contrast between the planet and the star. Figure 11 shows




Fig. 11. Example spectrum of the data at $2.0 \mu\text{m}$.

an example spectrum of the $2.0 \mu\text{m}$ data. The spectra on detectors 1 and 4 are dominated by telluric CO_2 lines, greatly reducing the potential for retrieving exoplanet signals. In detectors 2 and 3 water lines are also evident. In general, the telluric transmission is significantly lower than around $2.3 \mu\text{m}$. For this wavelength setting we ignored detector 4 because of the much lower count level. The SVD analysis could reduce the systematic signals to similar levels as in Fig. 1. Again, models with varying temperature profiles and volume mixing ratios of H_2O and CO_2 were inserted with $K_p = 154 \text{ km s}^{-1}$ to find $3\text{-}\sigma$ upper limits of 8.7×10^{-4} for H_2O and 1.8×10^{-3} for CO_2 .

4.3. Planet system parameters

Since we now have a measure of the velocity and the orbital inclination of both the star and the planet around their common barycentre, model-independent estimates of their masses can be obtained in the same way as for stellar eclipsing binaries for more than a century (e.g. Torres et al. 2010). Using the values and uncertainties from Triaud et al. (2009, see Table 2) for the amplitude of the stellar radial velocity variations, planet orbital inclination and period, we determine a stellar mass of $M_s = 0.846^{+0.068}_{-0.049} M_\odot$ and a planet mass of $M_p = 1.162^{+0.058}_{-0.039} M_{\text{Jup}}$. The stellar mass is consistent with that found by Triaud et al. (2009) ($M_s = 0.823^{+0.022}_{-0.029} M_\odot$ and $M_p = 1.138^{+0.022}_{-0.025} M_{\text{Jup}}$). In principle, if these CRILES observations are repeated on both sides of the secondary eclipse (phases higher and lower than 0.5) and also at somewhat higher planet radial velocities (phases closer to 0.25 or 0.75), the uncertainty in stellar mass can be reduced to a level of $\sim 1\%$. This is discussed in more detail in Sect. 5.

5. Discussion and conclusions

Using high-resolution spectra from CRILES on the VLT at orbital phases between 0.38–0.48, we detected carbon monoxide in the day-side atmosphere of HD 189733b at a $5\text{-}\sigma$ significance. From *Spitzer* data the presence of CO was already suspected (Barman 2008; Désert et al. 2009), although wider scans of the parameter space revealed no useful constraints on CO based on the *Spitzer* secondary eclipse data alone (Madhusudhan & Seager 2009). HST/NICMOS secondary eclipse data do show high CO volume mixing ratios ($\sim 10^{-4}$ – 10^{-2}) (Swain et al. 2009; Madhusudhan & Seager 2009; Lee et al. 2012), although previous NICMOS results have been received with

Table 2. Stellar and orbital parameters taken from Triaud et al. (2009) and derived from our measurements.

| Parameter (unit) | Value |
|--|--|
| Assumed parameters (Triaud et al. 2009): | |
| K_s (m s^{-1}) | $201.96^{+1.07}_{-0.63}$ |
| P (days) | $2.21857312^{+0.00000036}_{-0.00000076}$ |
| i ($^\circ$) | $85.508^{+0.10}_{-0.05}$ |
| Measured parameters: | |
| K_p (km s^{-1}) | 154^{+4}_{-3} |
| Derived parameters: | |
| M_s (M_\odot) | $0.846^{+0.068}_{-0.049}$ |
| M_p (M_{Jup}) | $1.162^{+0.058}_{-0.039}$ |




Fig. 12. Normalised contribution functions for a model spectrum with CO at a volume mixing ratio of 10^{-4} . These show where in the atmosphere the thermal flux is emitted for each wavelength.

some scepticism (e.g. Gibson et al. 2011). Waldmann et al. (2012) claimed to have detected a strong planet emission feature at $2.3 \mu\text{m}$ using low-resolution groundbased spectroscopy, similar to the controversial signal found at $3.2 \mu\text{m}$ by Swain et al. (2010), and also suggested it might be non-LTE emission. Because no proper physical model exists for this emission as yet, we were unable to perform a detailed search for this emission in our data. However, no obvious high-resolution signal, expected from the $\sim 2 \times 10^{-3}$ low-resolution signal seen by Waldmann et al., is present in our data. Figure 1 indicates that single lines cannot be seen above the 1% level in our data.

The CRILES measurements are not sensitive to the continuum level of the planet spectrum, because we removed any broadband signal in our data analysis. Instead, we determined an unconvolved line contrast (the depth of the deepest lines with respect to the continuum, divided by the stellar flux) of $(4.5 \pm 0.9) \times 10^{-4}$ for the strongest CO lines. This line contrast indicates the difference between the thermal flux coming from the continuum level at high pressure and the flux from the line cores, which probe very low pressures (see Fig. 12). The line contrast thus depends on the difference in temperatures at the pressures of the continuum and the line cores. Clearly, there is a strong degeneracy in the temperature structure of the atmosphere that can reproduce a certain line contrast, since different sets of temperatures can have the same difference in flux. Furthermore,




Fig. 13. The highest line contrasts (solid line) as a function of CO volume mixing ratio in our model grid (see Sect. 3). The lowest line contrast in a planetary atmosphere is zero for an isothermal atmosphere. Dashed lines show our determined limits on the CO line contrast.

the abundance of CO adds another ambiguity, since increasing the CO abundance will decrease the pressure that is probed by the line cores. It is therefore uncertain at what pressure the flux of the line cores originates. This also means that we cannot determine CO abundances from line contrasts alone. Figure 13 illustrates this point. It shows the highest line contrasts that were obtained in our model grid (see Sect. 3). Note that in this grid we kept temperatures fixed at pressures above 0.1 bar, meaning that we basically fixed the continuum level, which already reduced part of the possible degeneracies. Furthermore, our grid only covered a selected portion of the parameter space. A lower limit on the line contrast comes from an isothermal atmosphere, which would not show any lines (zero contrast). Figure 13 shows that there is practically no dependence of the range of possible line contrasts on the CO volume mixing ratio. Hence, more information is needed before the CO abundance can be determined from these kinds of high spectral resolution measurements, most notably the temperature profiles, which cover pressures from the continuum level to the low pressures of the line cores. Constraints on the temperature profile can be obtained by measuring the thermal flux (or secondary eclipse depths) at a range of wavelengths, probing a range of pressures generated by differences in gas absorption (e.g. Madhusudhan & Seager 2009; Line et al. 2012; Lee et al. 2012). However, lower resolution measurements do not probe the low pressures of the line cores well. There is also still a degeneracy with absolute gas abundances, since this determines the pressure levels that are probed. Ideally, one would have a single gas for which we know (or can estimate reliably) the absolute abundance, and which probes a wide range of pressures from absorption lines or bands of different strengths. From measurements of this gas at different wavelengths the temperature structure can then be determined if the variation of the gas abundance with pressure is known. CO₂ plays this role in the Venus atmosphere and CH₄ in the atmospheres of Jupiter, Saturn, and Titan. Obtaining absolute gas abundances for giant exoplanet atmospheres is possible using transit (transmission) measurements if the H₂ Rayleigh scattering slope is measured (e.g. Benneke & Seager 2012), although this signature might be difficult to distinguish from that of small haze particles. In summary, obtaining absolute gas abundances from line contrasts such as we present here is difficult, but the

line contrasts can be used as an additional constraint to reduce the uncertainty in retrievals. However, if multiple gases would be detected in a single high-resolution observation, this would make it possible to determine the relative abundances of these gases, since they would both rely on the same temperature profile with the same continuum level at the same time. There might still be some degeneracy caused by the line cores of the two gases probing two different ranges of pressures, but these pressure ranges are very likely to overlap.

In comparing our results with the claimed detection by Rodler et al. (2013), we note that the planet radial velocity measurements are consistent within their reported 1- σ error bars. Rodler et al. (2013) found a CO line contrast of 1.8×10^{-4} at a spectral resolution of $R = 25\,000$ with NIRSPEC at Keck. Assuming that the lines are unresolved, this translates into a line contrast of $\sim 7 \times 10^{-4}$ at the CRILES resolution, which is more than 50% higher than what we find in our study. This may suggest that the reliability of the Keck signal is somewhat overestimated. However, the error bars on the line contrast of Rodler et al. (2013) will probably be large, although these are not given in their paper. Rodler et al. (2013) suggest a possible low CO abundance based on their analysis of the Keck data. Our line contrast is potentially even lower, but unfortunately, we cannot yet draw conclusions on the CO abundance based on the line contrast alone (see the discussion above). Taking their 3- σ detection using 13 h of NIRSPEC observations at face value, the 5- σ detection presented here implies that CRILES is a factor 7 more efficient. We attribute this to the high spectral resolution and stability of CRILES, and the well-performing adaptive optics system on the VLT.

Based on the available secondary eclipse data, retrieval methods favour temperature profiles that decrease in temperature as pressure decreases, i.e. a temperature profile without an inversion layer (Madhusudhan & Seager 2009; Line et al. 2012; Lee et al. 2012). However, in a recent work Pont et al. (2013) argued that, based on their transmission measurements and improved analysis of secondary eclipse data, HD 189733b could also have temperatures that are increasing with decreasing pressure. This would then be the result of an optically thick haze layer, for which they see the signature in the transit measurements. However, our detection of CO shows that the temperature profile is not inverted at the pressures probed by the CO lines (10^{-5} – 10^{-3} bar for a CO volume mixing ratio of 10^{-4} , as seen in Fig. 12, and roughly an order of magnitude lower pressures for a CO volume mixing ratio of 10^{-3}) and that the CO lines are not obscured by an optically thick haze layer. In principle it is possible that we are only seeing the cores of the CO lines sticking out above the haze in a higher part of the atmosphere where the temperatures decrease again with altitude, but this would require large CO volume mixing ratios ($>10^{-4}$) if the temperature profile of Pont et al. (2013), which shows an inversion down to at least 0.1 mbar, is correct. Such a high CO abundance with absorption features above the haze layer would then also be visible around $5 \mu\text{m}$, where CO absorption is stronger than at $2.3 \mu\text{m}$. Such a CO feature might indeed be visible in *Spitzer* data (Knutson et al. 2012). An optically thick haze layer would also require a cold atmospheric layer above the haze layer, which is in contrast to the conclusions of Huitson et al. (2012). Hence, we conclude that the haze layer seen by Pont et al. (2008), Sing et al. (2009), and Pont et al. (2013) is either optically thin when seen at normal incidence angles and that consequently there is no temperature inversion in the middle atmosphere, or that the haze layer is optically thick, but low enough for CO lines to be visible.

We could derive only upper limits for the line contrasts of H₂O, CO₂, and CH₄: 8.7×10^{-4} for H₂O, 1.8×10^{-3} for CO₂ at 2.0 μm , 2.8×10^{-3} for H₂O, and 8.3×10^{-4} for CH₄ at 2.3 μm . Future observations, also at better suited wavelengths, will be needed to more effectively search for these gases and assess their relative abundances. A lower telluric absorption and higher planet-to-star contrast would be beneficial in these observations. However, it is not straightforward to identify an best wavelength for these observations. For instance, the planet-to-star contrast is better at longer wavelengths, but there the sky background increases. There is also a trade-off between targeting strong lines in the planet spectrum, while avoiding strong lines in the telluric spectrum. A sensitivity study covering the CRIRES wavelength range, using realistic instrument performance and telluric absorption spectra, is needed to determine the best wavelengths for detecting these gases using high-resolution spectroscopy. Note that the best observing wavelengths may differ for different targets.

From the measured radial velocity of $K_p = 154^{+4}_{-3} \text{ km s}^{-1}$ we derived a stellar mass of $M_s = 0.846^{+0.068}_{-0.049} M_\odot$ and a planet mass of $M_p = 1.162^{+0.058}_{-0.039} M_{\text{Jup}}$, independent of stellar spectral modelling. These values are consistent with previously known values and their errors are somewhat larger. However, combining these results with possible future observations at phases longer than 0.5, and phases closer to 0.25 and 0.75, would significantly help in reducing the error on K_p , and hence in the masses of the star and planet (e.g. Brogi et al. 2013). An error in K_p of 1 km s^{-1} would result in an error on the stellar mass of $0.017 M_\odot$, which is more precise than the current value derived from spectral modelling. The ability to treat transiting planet systems in the same manner as double-lined eclipsing binaries (DLEBs) allows a model-independent measurement of the stellar and planet masses and radii, which is particularly useful for planets with M-dwarf host stars. Precise dynamical measurements of the masses and radii of low-mass stars in DLEBs are not well-reproduced by stellar evolution models and have radii that are up to 15% larger than predicted (López-Morales & Ribas 2005; Ribas 2006). Strong magnetic fields in the short-period low-mass DLEBs are thought to be responsible for the radius inflation (see e.g. Chabrier et al. 2007; Morales et al. 2010). Even in higher mass G- and K-dwarfs, strong magnetic activity in the stars results in disagreement with stellar models (Morales et al. 2009). However, in wider separation M-dwarf DLEBs with magnetically inactive low-mass stars, the radii are still inflated (Irwin et al. 2011; Doyle et al. 2011), with no real convergence towards stellar models at longer periods (Birkby et al. 2012). Obtaining K_p for planets transiting M-dwarfs removes the uncertainty in stellar models and gives a direct and accurate characterisation of the star-planet system.

Acknowledgements. This work was funded by the Netherlands Organisation for Scientific Research (NWO). We are thankful to the ESO staff of Paranal Observatory for their support during the observations and we thank the referee for his or her insightful comments.

References

- Andrews, H. C., & Patterson, C. L. 1975, *The Am. Math Monthly*, 82, 1
- Arsenault, R., Alonso, J., Bonnet, H., et al. 2003, in *SPIE Conf. Ser.* 4839, eds. P. L. Wizinowich, & D. Bonaccini, 174
- Barman, T. S. 2008, *ApJ*, 676, L61
- Barnes, J. R., Barman, T. S., Jones, H. R. A., et al. 2010, *MNRAS*, 401, 445
- Benneke, B., & Seager, S. 2012, *ApJ*, 753, 100
- Birkby, J., Nefs, B., Hodgkin, S., et al. 2012, *MNRAS*, 426, 1507
- Borysow, A. 2002, *A&A*, 390, 779
- Borysow, A., Jorgensen, U. G., & Fu, Y. 2001, *J. Quant. Spectr. Rad. Transf.*, 68, 235
- Brogi, M., Snellen, I. A. G., de Kok, R. J., et al. 2012, *Nature*, 486, 502
- Brogi, M., Snellen, I. A. G., de Kok, R. J., et al. 2013, *ApJ*, 767, 27
- Chabrier, G., Gallardo, J., & Baraffe, I. 2007, *A&A*, 472, L17
- Charbonneau, D., Knutson, H. A., Barman, T., et al. 2008, *ApJ*, 686, 1341
- Deming, D., Harrington, J., Seager, S., & Richardson, L. J. 2006, *ApJ*, 644, 560
- Désert, J.-M., Lecavelier des Etangs, A., Hébrard, G., et al. 2009, *ApJ*, 699, 478
- Doyle, L. R., Carter, J. A., Fabrycky, D. C., et al. 2011, *Science*, 333, 1602
- Gibson, N. P., Pont, F., & Aigrain, S. 2011, *MNRAS*, 411, 2199
- Gibson, N. P., Aigrain, S., Pont, F., et al. 2012, *MNRAS*, 422, 753
- Grillmair, C. J., Burrows, A., Charbonneau, D., et al. 2008, *Nature*, 456, 767
- Huitson, C. M., Sing, D. K., Vidal-Madjar, A., et al. 2012, *MNRAS*, 422, 2477
- Irwin, J. M., Quinn, S. N., Berta, Z. K., et al. 2011, *ApJ*, 742, 123
- Kaeufl, H.-U., Ballester, P., Biereichel, P., et al. 2004, in *SPIE Conf. Ser.* 5492, eds. A. F. M. Moorwood, & M. Iye, 1218
- Kalman, D. 1996, *College Math Journal*, 27, 2
- Knutson, H. A., Charbonneau, D., Cowan, N. B., et al. 2009, *ApJ*, 690, 822
- Knutson, H. A., Lewis, N., Fortney, J. J., et al. 2012, *ApJ*, 754, 22
- Lee, J.-M., Fletcher, L. N., & Irwin, P. G. J. 2012, *MNRAS*, 420, 170
- Line, M. R., Zhang, X., Vasisth, G., et al. 2012, *ApJ*, 749, 93
- López-Morales, M., & Ribas, I. 2005, *ApJ*, 631, 1120
- Madhusudhan, N., & Seager, S. 2009, *ApJ*, 707, 24
- Mandell, A. M., Drake Deming, L., Blake, G. A., et al. 2011, *ApJ*, 728, 18
- Morales, J. C., Torres, G., Marschall, L. A., & Brehm, W. 2009, *ApJ*, 707, 671
- Morales, J. C., Gallardo, J., Ribas, I., et al. 2010, *ApJ*, 718, 502
- Moses, J. I., Madhusudhan, N., Visscher, C., & Freedman, R. S. 2013, *ApJ*, 763, 25
- Pont, F., Knutson, H., Gilliland, R. L., Moutou, C., & Charbonneau, D. 2008, *MNRAS*, 385, 109
- Pont, F., Sing, D. K., Gibson, N. P., et al. 2013, *MNRAS*, accepted [[arXiv: 1210.4163](https://arxiv.org/abs/1210.4163)]
- Redfield, S., Endl, M., Cochran, W. D., & Koesterke, L. 2008, *ApJ*, 673, L87
- Ribas, I. 2006, *Ap&SS*, 304, 89
- Rodler, F., Lopez-Morales, M., & Ribas, I. 2012, *ApJ*, 753, L25
- Rodler, F., Kürster, M., & Barnes, J. R. 2013, *MNRAS*, accepted [[arXiv: 1303.3131](https://arxiv.org/abs/1303.3131)]
- Rothman, L. S., Wattson, R. B., Gamache, R., Schroeder, J. W., & McCann, A. 1995, in *SPIE Conf. Ser.*, 2471, 105
- Rothman, L. S., & Gordon, I. 2009, *J. Quant. Spectr. Rad. Transf.*, 96, 139
- Rothman, L. S., Gordon, I. E., Barber, R. J., et al. 2010, *J. Quant. Spectr. Rad. Transf.*, 111, 2139
- Sing, D. K., Désert, J., Lecavelier Des Etangs, A., et al. 2009, *A&A*, 505, 891
- Snellen, I. A. G., de Kok, R. J., de Mooij, E. J. W., & Albrecht, S. 2010, *Nature*, 465, 1049
- Snellen, I., de Kok, R., de Mooij, E., et al. 2011, in *IAU Symp.* 276, eds. A. Sozzetti, M. G. Lattanzi, & A. P. Boss, 208
- Swain, M. R., Vasisth, G., & Tinetti, G. 2008, *Nature*, 452, 329
- Swain, M. R., Vasisth, G., Tinetti, G., et al. 2009, *ApJ*, 690, L114
- Swain, M. R., Deroo, P., Griffith, C. A., et al. 2010, *Nature*, 463, 637
- Torres, G., Andersen, J., & Giménez, A. 2010, *A&ARv*, 18, 67
- Triaud, A. H. M. J., Queloz, D., Bouchy, F., et al. 2009, *A&A*, 506, 377
- Waldmann, I. P., Tinetti, G., Drossart, P., et al. 2012, *ApJ*, 744, 35
- Welch, M. B. 1947, *Biometrika*, 34, 28